



This document replaces the previously published Architectural/Engineering Guidelines (Revised February, 2008).

Additional revisions to the Guidelines/Standards will be issued from time to time to reflect the latest TFC practices. The electronic version of this document is available on-line at <http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex/> and contains hyperlinks to referenced documents and relevant internet web-sites as well as pertinent locations within the document itself.





TABLE OF CONTENTS

TABLE OF CONTENTS 2

ABBREVIATIONS 3

GUIDELINES / STANDARDS - PURPOSE..... 5

STATE AGENCIES..... 6

STATUTORY REQUIREMENTS 7

SUBMISSION PROCEDURES 13

 Round Trip Review Process Diagram 16

SUBMISSION MILESTONES 17

SUBMISSION CONTENT 19

 Mobilization / Pre-design 19

 Schematic Design 25

 Design Development..... 31

 Contract Documents 38

 Contract Bidding & Award 42

 Construction 44

 Warranty..... 45

DRAWING STANDARDS - DOCUMENT ORGANIZATION..... 46

CADD / BIM STANDARDS – OVERVIEW 48

CADD STANDARDS 49

BIM STANDARDS 53

 BIM Standards - File Types 53

 Revit View Settings 57

 Revit Partitions 59

 Revit Door Types 62

 Revit Room Styles..... 65

 Revit Materials 66

 Recommended Practices 71

APPENDICES 72

WEB LINKS INCLUDED IN THIS DOCUMENT..... 73

INDEX 77



| ABBREVIATIONS - GENERAL | | | |
|-------------------------------|---|-----------------------------|---|
| <u>ADA</u> | Americans With Disabilities Act | <u>IPD</u> | Internal Procurement Division (TFC) |
| <u>ADAS</u> | ADA Standards | <u>LDC</u> | Land Development Code (City of Austin) |
| <u>AHJ</u> | Authority Having Jurisdiction | <u>LJA</u> | Local Jurisdictional Authority(ies) – Building Plan Review, Site Plan Review, Utility Providers, Fire Department... |
| <u>ANSI</u> | American National Standards Institute | <u>NFPA</u> | National Fire Protection Association |
| <u>ASHRAE</u> | The American Society of Heating, Refrigerating and Air-Conditioning Engineers | <u>OAC</u> | Owner / Architect / Contractor |
| <u>BMS</u> | Building Management System | <u>OM</u> | Operations and Maintenance (TFC) |
| <u>BIM</u> | Building Information Modeling | <u>PAM</u> | Property and Asset Management (TFC) |
| <u>CADD</u> | Computer Aided Design and Drafting | <u>PDF</u> | Adobe Acrobat file type |
| <u>CHP</u> | Combined Heating and Power System | <u>PSP</u> | Professional Service Provider |
| <u>COA</u> | City of Austin | <u>RVT</u> | Autodesk Revit file type |
| <u>DIR</u> | Department of Information Resources | <u>SECO</u> | State Energy Conservation Office |
| <u>DPM</u> | Director of Project Management (TFC) | <u>SFMO</u> | State Fire Marshal's Office |
| <u>DPS</u> | Department of Public Safety | <u>SGC</u> | Supplementary General Conditions |
| <u>DWF</u> | Autodesk Design Review file type | <u>TAC</u> | Texas Administrative Code |
| <u>DWG</u> | Autodesk Autocad file type | <u>TAS</u> | Texas Accessibility Standards |
| <u>EAB</u> | Elimination of Architectural Barriers | <u>TCEQ</u> | Texas Commission on Environmental Quality |
| <u>EM</u> | Energy Management (TFC) | <u>TDLR</u> | Texas Department of Licensing and Regulation |
| <u>EPMCS</u> | Electronic Project Management Control System (TFC) | <u>TDI</u> | Texas Department of Insurance |
| <u>FDC</u> | Facilities Design and Construction (TFC) | <u>TFC</u> | Texas Facilities Commission |
| <u>HSC</u> | Health & Safety Code (Texas) | <u>TGC</u> | Texas Statutes - Government Code |
| <u>HUB</u> | Historically Underutilized Business Program (TFC) | <u>THC</u> | Texas Historical Commission |
| <u>ICC</u> | International Code Council | <u>PS</u> | Project Support (TFC-FDC) |
| <u>IMPACT</u> | TFC's Internet-based "Project Management Control System" | <u>UA</u> | Using Agency(ies) |
| | | <u>UGC</u> | Uniform General Conditions |

[Return to Table of Contents](#) * See next page for more Abbreviations.



| ABBREVIATIONS – DESIGN DISCIPLINES | | | |
|---|----------------------------|-------------|-------------------------|
| ACOU | Acoustical | INT | Interiors |
| ARCH | Architecture | KIT | Kitchen |
| CIV | Civil Engineering | LAR | Landscape Architecture |
| COMM | Data/Communications | MECH | Mechanical Engineering |
| ELEC | Electrical Engineering | PLUM | Plumbing Engineering |
| FA | Fire Alarm | SEC | Security/Access Control |
| FURN | Furniture | STRU | Structural Engineering |
| GEN | General (Cover / Index...) | | |

| ABBREVIATIONS – PROJECT PHASES | | | |
|---------------------------------------|--------------------------------------|-----------|---------------------------|
| BA | Contract Bidding & Award | MP | Mobilization / Pre-Design |
| CA | Construction Contract Administration | PA | Project Analysis |
| CD | Contract Documents | RD | Record Documents |
| DD | Design Development | SD | Schematic Design |

[Return to Table of Contents](#)



| GUIDELINES / STANDARDS - PURPOSE | | |
|----------------------------------|--|---|
| TOPIC | INFORMATION | LINKS |
| Applicability | A. This document applies to all TFC projects contracted on or after the Edit Date indicated in the header above. | |
| Intent | A. Identify TFC preferred procedures, systems, and materials; and B. Aid the PSPs in delivering professional services resulting in facilities that meet or exceed TFC project and performance goals. C. The Guidelines/Standards are not intended to replace or circumvent the informed professional judgment of planning, design, and construction Professional Service Providers (PSPs). D. Professional judgment leading to recommendations that differ from these Guidelines/Standards must be communicated in writing through TFC’s Project Manager (PM) for consideration and determination by TFC. | |
| Periodic Revisions | A. Revisions to the Guidelines/Standards will be issued from time to time to reflect the latest TFC practices, but only currently issued versions will be posted on the FDC Forms Index page of TFC’s website. B. A project commencing under a specific Guidelines/Standards issue date may continue on the basis of that issue; however, it is the PSP’s responsibility to keep a copy of the relevant Guidelines/Standards. | <ul style="list-style-type: none"> · FDC Forms Index |
| TFC Statutory Charge | A. Determining, creating, and protecting long term value in the public's investment for housing state government programs and functions. B. Texas Government Code (TGC) Chapter 2165 states that TFC: 1. "...has charge and control of all public buildings, grounds, and property..."; and 2. "...is the custodian of all state personal property...". C. Exceptions exist for certain named agencies and Higher Education. | <ul style="list-style-type: none"> · TGC 2165 |
| Software Requirements | A. TFC has established CADD software as a means for producing the design and documentation for all projects developed under TFC authority. B. Building Information Modeling (BIM) software may be used in lieu of CADD for any project developed under TFC authority. C. TFC-accepted CADD and BIM software versions are listed in the "CADD/BIM Standards - Overview" section of this document. | <ul style="list-style-type: none"> · CADD/BIM Standards · CADD Standards · BIM Standards |

[Return to Table of Contents](#)

[Abbreviations](#)



| STATE AGENCIES | | |
|--|---|--|
| Entity | DESCRIPTION | LINKS |
| Texas Facilities Commission (TFC) | A. Agent for the State of Texas; B. "Owner" and/or "Lessor" for capital construction and leasing projects. C. TFC Divisions: <ol style="list-style-type: none"> 1. Facilities Design and Construction (FDC): <ol style="list-style-type: none"> a. Represents TFC in its capital construction projects; b. Assigns a Project Manager (PM) to each project. 2. Property and Asset Management (PAM): <ol style="list-style-type: none"> a. Reviews and approves space allocations for Using Agencies; 3. Energy Management(EM): <ol style="list-style-type: none"> a. Monitors and evaluates energy consumption and provides recommendations for energy saving improvements. 4. Operations and Maintenance (OM): <ol style="list-style-type: none"> a. Operates and maintains building systems for properties included in the TFC inventory.. 5. Internal Procurement Division (IPD): <ol style="list-style-type: none"> a. Procures goods and services for use by TFC including but not limited to: <ol style="list-style-type: none"> i. Construction Services; and ii. Professional services such as architectural and engineering services. | <ul style="list-style-type: none"> • TFC • FDC • PAM • EM • OM • IPD |
| Using Agency (UA) | A. The agency (or agencies) for which TFC manages the design and construction process of a project. | |
| Other Key Agencies | A. Department of Public Safety, Capitol District (DPS): <ol style="list-style-type: none"> 1. Administers the Austin area parking programs for TFC facilities; 2. Provides physical security for state personnel and property; and 3. Installs Capital area keyways and keys. B. Elimination of Architectural Barriers (EAB) - Texas Department of Licensing & Regulation's division responsible for certification of all plans and specifications for accessibility to persons with disabilities in accordance with the Texas Architectural Accessibility Standard. C. State Energy Conservation Office (SECO) - responsible for developing and administering standards for energy efficient design for state buildings and facilities. D. Department of Information Resources Telecommunications (DIR) - operates the local Capitol Complex telephone systems, a statewide long distance network and consults on telecommunication aspects of projects throughout the state. | <ul style="list-style-type: none"> • DPS • TDLR • EAB • SECO • DIR |



| STATUTORY REQUIREMENTS | | |
|----------------------------------|--|--|
| REQUIREMENT | SUMMARY DESCRIPTION | LINKS |
| General | A. TFC statutory requirements of general interest to the PSP or that require PSP compliance include but are not limited to the following: | <ul style="list-style-type: none"> • TGC 2151 • TGC 2152 • TGC 2155 • TGC 2156 • TGC 2157 • TGC 2158 • TGC 2161 • TGC 2162 • TGC 2163 • TGC 2165 • TGC 2166 • TGC 2167 |
| TFC Enabling Statute | A. The Texas Facilities Commission Act, Articles 2151 through 2167, Texas Government Code (TGC) establishes the authority of the Texas Facilities Commission. | |
| FDC Activities and Limits | A. TGC Chapter 2166 generally describes the activities and limits of the Facilities Design and Construction division of TFC. | |
| Project Funding | <p>A. TGC Chapter 2166.251(c) "The appropriation of funds by the legislature for the construction of a project shall be construed by TFC and the using agency as an expression of legislative intent that the project be completed within the limits of the funds actually appropriated ..."</p> <p>B. The State's goal is to include all project requirements in the bid documents to assure that all aspects of the project have been competitively bid thereby resulting in the best value for the State.</p> | |
| Change Orders | A. TGC Chapter 2166.257 - No additive change order may be authorized without approval by the PSP, the UA, and FDC's DED. | |
| Document Review | <p>A. TGC Chapter 2166.156(c) "...ensure that [preliminary and working] plans and specifications" for all facilities constructed for the purpose of housing a State of Texas agency (or agencies):</p> <ul style="list-style-type: none"> a. "Are clear and complete; b. Permit execution of the project with appropriate economy and efficiency; and c. Conform with the requirements described by the Project Analysis". <p>B. TGC Chapter 2166.156(d) "...approve plans and specifications before the Using Agency(ies) may accept or use them."</p> | |

[Return to Table of Contents](#)

* See next page for additional Statutory Requirements.

[Abbreviations](#)



| STATUTORY REQUIREMENTS | | (CONTINUED) |
|--|---|---|
| REQUIREMENT | SUMMARY DESCRIPTION | LINKS |
| Storm Water Pollution Prevention Plan | A. As applicable, projects may require a Storm Water Pollution Prevention Plan (SWPPP) per TCEQ. | <ul style="list-style-type: none"> • TCEQ Construction Activities Regulations |
| Capitol Views | A. Compliance with the most restrictive of the following is required: B. TGC Chapter 3151; and C. COA Land Development Code, 25-2-161, 162, 641, 642 and Appendix A. | <ul style="list-style-type: none"> • TGC 3151 • COA - LDC |
| Energy / Water Conservation | A. For leased and state owned facilities, TAC Title 34, Chapter 19, Subchapter B requires state agencies to: <ol style="list-style-type: none"> 1. "...ensure preparation of a Resource Efficiency Plan..."; 2. Certify to [SECO] that the plan has been completed; and 3. "...implement the cost effective utility conservation measures in accordance with ... the agency's Resource Efficiency Plan...". B. TGC Section 447.004 requires compliance with SECO's "The Energy Conservation Design Standard for New State Buildings". C. All design must comply with ASHRAE 90.1-(currently adopted edition) and furnish evidence of compliance with energy efficiency and water conservation standards published by SECO. D. TGC Sections 2166.404 and 2166.405 require all projects to be designed for water conservation including irrigation and xeriscape planting. E. HSC 372.002 - Water saving performance standards; | <ul style="list-style-type: none"> • TAC • SECO • SECO Suggested Water Efficiency Standards • TGC 447.004 • ASHRAE Standards / Guidelines • TGC 2166.404 and 2166.405 • HSC 37.002 |

[Return to Table of Contents](#)

* See next page for additional Statutory Requirements.

[Abbreviations](#)



| STATUTORY REQUIREMENTS | | (CONTINUED) |
|---|---|--|
| REQUIREMENT | SUMMARY DESCRIPTION | LINKS |
| <p>Energy Efficient Architectural and Engineering Design Alternatives Evaluation</p> | <p>A. TGC 2166.403 - All new building construction projects require a written economic feasibility evaluation of incorporating energy alternatives and energy-efficient architectural and engineering design into the building's design and proposed energy system.</p> <ol style="list-style-type: none"> 1. Alternative Energy is defined as a renewable energy resource including solar energy, biomass energy, geothermal energy, and wind energy. 2. SECO must approve any methodology or electronic software used in the analysis. 3. The evaluation must identify the best energy alternative for each function of the project over the economic life of the building considering costs and benefits of implementing alternative design practices and energy systems for all or part of each function relative to the use of conventional design practices and energy systems. 4. The evaluation must be made available to the public and presented at an open meeting. 5. If alternative designs or energy systems are determined to be economically feasible, the alternative design or system must be incorporated into the project. | <ul style="list-style-type: none"> • TGC 2166.403 • SB 982 - SECO Approved Methodologies |

[Return to Table of Contents](#)

* See next page for additional Statutory Requirements.

[Abbreviations](#)



| STATUTORY REQUIREMENTS | | (CONTINUED) |
|---|---|--|
| REQUIREMENT | SUMMARY DESCRIPTION | LINKS |
| <p>Combined Heating and Power (CHP) System</p> | <p>A. TGC 2311.002 – For economic development programs involving both state and local governments, new construction and extensive HVAC equipment renovations to critical governmental facilities require evaluation of the economic feasibility (over a 20 year period) of equipping the facility with a Combined Heating and Power (CHP) system.</p> <p>1. A critical government facility is defined as a building owned by the state or a political subdivision of the state that is expected to:</p> <ul style="list-style-type: none"> a. Be continuously occupied; b. Maintain operations for at least 6,000 hours each year; c. Have a peak electricity demand exceeding 500 kilowatts; and d. Serve a critical public health or public safety function during a natural disaster or other emergency situation that may result in a widespread power outage, including a: <ul style="list-style-type: none"> i. Command and control center; ii. Shelter; iii. Prison or jail; iv. Police or fire station; v. Communications or data center; vi. Water or wastewater facility; vii. Hazardous waste storage facility; viii. Biological research facility ix. Hospital; or x. Food preparation or food storage facility. | <ul style="list-style-type: none"> · TGC 2311.002 |

[Return to Table of Contents](#)

* See next page for additional Statutory Requirements.

[Abbreviations](#)



| STATUTORY REQUIREMENTS | | (CONTINUED) |
|---|--|--|
| REQUIREMENT | SUMMARY DESCRIPTION | LINKS |
| Exterior Lighting/Lighting Pollution | A. Health and Safety Code, Title 5, Subtitle F, Chapter 425 requires outdoor lighting fixtures to be cutoff type luminaires under specific circumstances. | <ul style="list-style-type: none"> • HSC 425 |
| Codes and Standards | <p>A. The most restrictive requirements of the following codes and standards will govern:</p> <ol style="list-style-type: none"> 1. NFPA 101 Life Safety Code - Latest adopted edition per SFMO (TGC 417.008(e) establishes the SFMO as the AHJ for fire safety in all state owned buildings). 2. International Code Council (ICC) family of codes (latest published editions). 3. NFPA 70: National Electrical Code (latest published edition). 4. NFPA 70E: Standard for Electrical Safety in the Workplace; 5. ASHRAE 90.1: Energy Conservation Design Standard for State-Funded Buildings (latest adopted edition per SECO); 6. Americans With Disabilities Act of 1990 (as currently amended); <ol style="list-style-type: none"> a. 2010 ADA Standards for Accessible Design – 2010 Standards for State and Local Governments Title II; 7. TGC Chapter 469, Elimination of Architectural Barriers; <ol style="list-style-type: none"> a. 2012 Texas Accessibility Standards (and Technical Memoranda). <p>B. State of Texas properties are not subject to municipal or local codes, however TFC projects should be generally consistent with local land use practices. Cooperation with local services such as fire, watershed and utilities is advantageous to TFC projects.</p> | <ul style="list-style-type: none"> • TGC 417.008 • NFPA 101 • NFPA 101 - SFMO Adoption • ICC Store • ICC Free E-Codes • NFPA 70 (NEC) • NFPA 70E • ASHRAE Standards / Guidelines • ASHRAE 90.1 – SECO Adoption • ADA Standards • TGC 469 • TAS Standards • Architectural Barriers Technical Memoranda |

[Return to Table of Contents](#)

* See next page for additional Statutory Requirements.

[Abbreviations](#)



| STATUTORY REQUIREMENTS | | (CONTINUED) |
|---|---|---|
| REQUIREMENT | SUMMARY DESCRIPTION | LINKS |
| Hazardous Materials | <p>A. Prior to demolition or construction efforts on existing facilities;</p> <p>a. TAC, Title 25, Part 1, Chapter 295, Subchapter C, Rule 295.34 requires building owners to:</p> <p>i. Survey the facility for asbestos-containing material (ACM);</p> <p>ii. Abate all asbestos-containing building material (ACBM) that could foreseeably be disturbed in the area to be renovated; and</p> <p>iii. Perform abatement in accordance with the Federal National Emission Standard for Asbestos (40 CFR, Chapter 61, Subpart M)</p> <p>b. Obtain certification by a licensed engineer or architect that:</p> <p>i. In the engineer's or architect's professional opinion, all parts of the building affected by the planned renovation or demolition do not contain asbestos."</p> <p>ii. Certification may be based on:</p> <p>(a) Current or previous surveys and reports;</p> <p>(b) Material safety data sheets for the materials used in</p> <p>(i) The original construction; and</p> <p>(ii) The subsequent renovations or alterations of all parts of the building affected by the planned renovation or demolition.</p> | <ul style="list-style-type: none"> • TAC, 25,1, 295, C, 295.34 |
| Uniform and Supplementary General Conditions | <p>A. TGC Chapter 2166.302 requires TFC to adopt "...uniform general conditions to be incorporated into all building construction contracts made by the state".</p> <p>1. TFC's Supplementary General Conditions modify the UGC and are required by TFC to also be incorporated into all TFC construction contracts.</p> <p>2. TFC's currently adopted UGC and SGC are available on the TFC website.</p> <p>B. TFC has also developed Special Conditions that may be incorporated in construction contracts at the discretion of TFC.</p> <p>1. TFC Special Conditions, when required, may be obtained through TFC's PM.</p> | <ul style="list-style-type: none"> • TGC 2166.302 • UGC / SGC |
| Site Inspections | <p>A. TGC Chapter 2166.351 - TFC is responsible for protecting the interests of the state during construction through appropriate levels of inspections, including requirements upon the PSP.</p> | <ul style="list-style-type: none"> • TGC 2166.351 |

[Return to Table of Contents](#)

[Abbreviations](#)



| SUBMISSION PROCEDURES | | |
|----------------------------------|---|---|
| PROCEDURE | PSP ACTIONS REQUIRED | LINKS |
| General | <p>A. TFC has adopted an electronic “Round Trip” review process intended to:</p> <ol style="list-style-type: none"> 1. Maximize clarity of communications between TFC and PSPs; 2. Minimize document review turn-around time; and 3. Reduce the environmental impact created by the traditional method of printing and transporting hard-copy documents. <p>B. Submit all documentation required at each project milestone as required in this section and in the Submission Milestones and Submission Content sections below.</p> <p>C. Clearly indicate the appropriate Edit Date of the Guidelines / Standards applicable to the project being submitted for review.</p> | <ul style="list-style-type: none"> • Round Trip Review Process • Submission Milestones |
| Electronic Documents (Soft Copy) | <p>A. Drawings: At each submission milestone:</p> <ol style="list-style-type: none"> 1. Publish, or Export (do not scan) drawing sheet views to “DWF” format; 2. Group sheets into separate files by design discipline using the following file naming convention: <div style="text-align: center;"> <p>00-000-0000_??_??_??</p> <p>↑ Underscore</p> </div> <p>B. BIM Models (when provided): At each submission milestone:</p> <ol style="list-style-type: none"> 1. Civil3D Files: <ol style="list-style-type: none"> a. Update the “.adsk” file(s) exported from the Building Model(s); and b. W-Block out information in “.dwg” file format. 2. Revit Files: <ol style="list-style-type: none"> a. “Synchronize” all Revit “Local Files” with the “Central Model File”, and Export the “Central Model File” to “.adsk” (only for projects that require coordination with Civil3D files). | <ul style="list-style-type: none"> • Autodesk “DWF Writer” • Drawing Standards – Document Organization • BIM Standards |

[Return to Table of Contents](#)

* See next page for additional Submission Procedure requirements.

[Abbreviations](#)



SUBMISSION PROCEDURES (CONTINUED)

| PROCEDURE | PSP ACTIONS REQUIRED | LINKS |
|--|---|--|
| <p>Electronic Documents (Soft Copy) (Continued)</p> | <p>C. Specifications: At each submission milestone:</p> <ol style="list-style-type: none"> 1. Print (do not scan) all specification sections to DWF format (use Autodesk’s free “DWF Writer” program); 2. Group specifications into separate files by Division Number; 3. Name division files using the following file naming convention: <div style="text-align: center;"> <p>00-000-0000_???_???_SPEC_##</p> </div> <p>D. Transmit all electronic files to TFC.</p> | <ul style="list-style-type: none"> • Submission Milestones • Autodesk “DWF Writer” |
| <p>Printed Documents (Hard Copy)</p> | <p>A. At each submission milestone:</p> <ol style="list-style-type: none"> 1. Print complete set of Drawings and Specifications; 2. Deliver complete, bound document sets to TFC’s PM; and 3. Notify TFC’s PM that the printed documents have been sent. | |
| <p>Respond to Owner Comments</p> | <p>A. Insert the DWF Mark-Up file into the appropriate CADD file or BIM Model as applicable;</p> <p>B. Modify the CADD file or BIM Model as appropriate to address Owner comments;</p> <p>C. While still in the CADD file or BIM Model:</p> <ol style="list-style-type: none"> 1. Select each mark-up as it is addressed and modify the “Status” and “Notes” properties to indicate that the comment was addressed and how it was addressed. 2. For CADD files, republish the DWF; 3. For BIM models, save the markup; <p>D. Transmit all electronic files to TFC.</p> | |

[Return to Table of Contents](#)

* See next page for additional Submission Procedure requirements.

[Abbreviations](#)




| SUBMISSION PROCEDURES | | (CONTINUED) |
|---|---|--|
| PROCEDURE | PSP ACTIONS REQUIRED | LINKS |
| SECO Compliance Form(s) | A. Submit the completed compliance certification form and supporting documentation to the PM: 1. For downloadable compliance forms, follow the link to the right (SECO's Building Codes and Standards web page). | <ul style="list-style-type: none"> • SECO – Texas Design Standard Compliance Forms |
| Accessibility Review and Inspection | A. Register project with TDLR and pay registration fee; B. Submit proof of registration and sealed Contract Documents to TDLR or an RAS within the allotted time; C. Pay the review fee; D. Respond in writing to TDLR or the RAS regarding measures to be taken to address any conditions found to be non-compliant and issue a formal Addendum correcting the deficiencies; E. Schedule the accessibility inspection on or after the date of substantial completion; F. Pay the inspection fee; G. Respond in writing to TDLR or the RAS regarding measures to be taken to address any conditions found to be non-compliant and issue a formal Change Proposal or directive. H. Provide TFC's PM with copies of all communications with TDLR and/or the RAS. | <ul style="list-style-type: none"> • TDLR Online Registration • TDLR Fee Schedule • TDLR Document Submission Requirements |
| Historical Status Determination and Compliance | A. If the Project Analysis indicates a requirement for THC review and approval, submit required documentation directly to THC in a timely manner. | <ul style="list-style-type: none"> • THC |
| TCEQ Documentation | A. For projects where a SWPPP is required, submit the necessary documentation to TCEQ and pay all application and review fees. | <ul style="list-style-type: none"> • TCEQ |

[Return to Table of Contents](#)

[Abbreviations](#)



SUBMISSION PROCEDURES – ROUND TRIP REVIEW PROCESS DIAGRAM



[Return to Table of Contents](#)

[Abbreviations](#)



| SUBMISSION MILESTONES | | |
|---------------------------------------|---|---|
| PHASE | MILESTONE DESCRIPTION | SUBMISSION FORMAT |
| General | A. Submit documentation for Owner review at each submission milestone listed below. B. Individual project requirements (as determined by TFC) may dictate the need for fewer or additional submissions and submission format changes - confirm specific requirements with PM. C. Submission content requirements are provided in the "Submission Content" portion of this document. | |
| Mobilization / Pre-design (MP) | A. MP1 - End of Phase - : 1. Substantially complete documentation of the work required in this design phase. 2. Final draft summarizing the decisions made to date. B. MP2 - Final Program : 1. Final programming documentation satisfactorily addressing <u>Owner</u> comments on previous submission. | <ul style="list-style-type: none"> · 3 printed and bound sets; and · Transmit electronic files to TFC. |
| Schematic Design (SD) | A. SD1 - End of Phase : 1. Substantially complete documentation of the work required in this design phase; and 2. Final draft summarizing the decisions made to date. B. SD2 - Final Presentation : 1. Final schematic documentation satisfactorily addressing Owner comments on previous submissions. 2. Presentation materials for the purpose of obtaining approval by TFC's commissioning board. | <ul style="list-style-type: none"> · 3 printed and bound sets; · Transmit electronic files to TFC; and · 3 mounted copies of renderings: <ul style="list-style-type: none"> ○ Image width 24" (min.) ○ Board width 30" (min.) |
| Design Development (DD) | A. DD1 - End of Phase : 1. Complete, coordinated documentation of the work required in this design phase except MEP documentation. B. DD2 - MEP End of Phase : 1. Complete, coordinated documentation of the MEP work required in this design phase. | <ul style="list-style-type: none"> · 3 printed and bound sets; and · Transmit electronic files to TFC. |

[Return to Table of Contents](#)

[Abbreviations](#)



| SUBMISSION MILESTONES | | (CONTINUED) |
|--|---|---|
| Contract Documents (CD) | <p>A. CD1 - Mid-Phase:</p> <ol style="list-style-type: none"> 1. In progress documentation of all work required in this design phase. 2. Submission occurs at approximately the mid-point of this design phase. 3. Satisfactorily address Owner comments on previous submissions. <p>B. CD2 - End of Phase:</p> <ol style="list-style-type: none"> 1. Substantially complete, coordinated documentation of all work required in this design phase. 2. Satisfactorily address Owner comments on previous submissions. | <ul style="list-style-type: none"> • 4 printed and bound sets; and • Transmit electronic files to TFC. |
| Contract Bidding and Award (BA) | <p>A. BA - Bid Documents:</p> <ol style="list-style-type: none"> 1. Satisfactorily address Owner comments on previous submission materials. 2. Complete, fully coordinated Bid Documents with: <ol style="list-style-type: none"> a. Professional seals affixed; and b. Signatures of all responsible design professionals. 3. Submit all necessary documentation to authorities having jurisdiction. | <ul style="list-style-type: none"> • Printed and bound sets (number defined in Contract); and • Transmit electronic files to TFC. |
| General Administration of Construction Contracts (CA) | <p>A. CA – Construction Phase Documents:</p> <ol style="list-style-type: none"> 1. Consolidated set of sealed / signed documents incorporating all Addenda and Clarifications issued during the bidding phase. | <ul style="list-style-type: none"> • 3 printed and bound sets; • Transmit electronic files to TFC. |
| Warranty (RD) | <p>A. RD – Record Documents:</p> <ol style="list-style-type: none"> 1. Documentation of as-constructed conditions. | <ul style="list-style-type: none"> • 3 printed and bound sets; and • Transmit electronic files to TFC. |

[Return to Table of Contents](#)

[Abbreviations](#)



| SUBMISSION CONTENT – MOBILIZATION / PRE-DESIGN (MP1 & MP2) | | |
|---|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| General | A. Confirm or modify to reflect current project requirements and/or conditions: <ol style="list-style-type: none"> 1. Prior programming decisions provided by TFC; 2. Existing conditions documents and other information provided by TFC. | |
| Executive Summary Report | A. Document relevant data collected, analyses performed, and design concepts and criteria recommended. B. Include: <ol style="list-style-type: none"> 1. An illustration of key conceptual issues; 2. Stacking and Blocking diagrams showing efficient use of space; 3. Summary of site evaluation and regional data. | <ul style="list-style-type: none"> · Autodesk Design Review (.dwf or .dwt) · TFC Accepted Software Versions |
| Project Objective Statement | A. State whether the project follows or deviates from the Project Analysis and why. | |
| Project Implementation Plan | A. Outline the method by which the project will be organized and delivered. | |
| Schedule for Delivery of Services | A. Identify all project milestones including: <ol style="list-style-type: none"> 1. Design Document Submission Dates and Review Periods for Owner and Jurisdictional Authorities: <ol style="list-style-type: none"> a. Submission; b. Review; c. Revision; and d. Authorization to Proceed. 2. Critical Meetings / Presentations; 3. Bid Package Issuance Date(s); 4. Bid Opening Date(s); 5. Construction start, punch inspection, and substantial completion; 6. Owner Move-in; and 7. Warranty Period. | |

[Return to Table of Contents](#)

* See next page for additional Mobilization / Pre-design Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – MOBILIZATION / PRE-DESIGN (MP1 & MP2) | | (CONTINUED) |
|--|---|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Preliminary Estimate of Probable Construction Cost | <p>A. Adjust the TFC provided project budget to reflect updated program requirements with the following basis for Unit Costs:</p> <ol style="list-style-type: none"> 1. Anticipated square footage (from Space Allocation Program below) 2. Recent comparable projects of similar function, size, construction type, level of finish, and type of mechanical and electrical system(s); 3. Adjust unit costs for local bidding climate at time of projected bid date. <p>B. Organize the estimate according to CSI Unifomat categories;</p> <ol style="list-style-type: none"> 1. Include all applicable assemblies and systems. <p>C. Include a list of items that are:</p> <ol style="list-style-type: none"> 1. Not in the contract; or 2. Supplied by others. <p>D. Include contingencies for the following:</p> <ol style="list-style-type: none"> 1. Scope escalation; 2. Development of unanticipated design elements; 3. Economic influences on cost escalation / fluctuation; and 4. Construction phase changes. <p>E. Identify cost variances between the Estimate and the established Construction Cost Limitation;</p> <p>F. Propose strategies for reconciling the variances.</p> | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwx) • TFC Accepted Software Versions |
| Technical Requirements List | <p>A. Submit a list of all applicable:</p> <ol style="list-style-type: none"> 1. Codes and Standards; 2. Jurisdictional Authorities; 3. Utility Providers; 4. Environmental factors affecting the project design (including EPA and TCEQ fuel storage requirements); 5. Applicable TFC Technical and Design Standards (Reference the applicable Edit Date); 6. Applicable Using Agency(ies) Technical and Design Standards (Reference the applicable Edit Date); <p>B. Provide Plumbing Fixture Count Calculations (based on Space Allocation Program below).</p> | |

[Return to Table of Contents](#)

* See next page for additional Mobilization / Pre-design Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – MOBILIZATION / PRE-DESIGN (MP1 & MP2) | | (CONTINUED) |
|--|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Existing Facilities Condition Analysis | A. Describe the condition of the existing building and / or site features: <ol style="list-style-type: none"> 1. Provide a list of all items to be relocated or reused; 2. Indicate all features that do not meet Programmatic or Technical Requirements; 3. Describe specific deficiencies for each non-compliant feature; and 4. Propose strategies for reconciling the deficiencies. | |
| Room Data Sheets | A. Provide the following information for each programmed space: <ol style="list-style-type: none"> 1. Structural / Physical Isolation; 2. Hazardous Materials List (Types & Quantities); 3. Fire Separation; 4. Acoustical Performance; 5. Access Control / Monitoring; 6. Door Information: <ol style="list-style-type: none"> a. Type(s); b. Size(s); c. Material(s); and d. Hardware Functions. 7. Finish Materials; 8. HVAC; <ol style="list-style-type: none"> a. Temperature Range(s); b. Humidity Control; c. Filtering; 9. HVAC and Lighting controls requirements; 10. Lighting Level (Foot Candles); 11. Electrical Power; 12. Data / Telecommunications; 13. Plumbing; 14. Re-used Items; and 15. Special Considerations. | <ul style="list-style-type: none"> · Autodesk Design Review (.dwf or .dwx) · TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Mobilization / Pre-design Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – MOBILIZATION / PRE-DESIGN (MP1 & MP2) | | (CONTINUED) |
|--|---|--|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Layout Diagrams | <p>A. Provide the following graphic information for each programmed space:</p> <ol style="list-style-type: none"> 1. Diagrammatic configuration of individual and/or groups of spaces; 2. Dimensional Requirements (absolute, minimum, and/or maximum); 3. Partition Type(s): <ol style="list-style-type: none"> a. Height; b. Fire Rating; and c. Sound Rating. 4. Door Location(s); 5. Window Location(s); 6. Furniture / Casework / Equipment / Relocated Items; <ol style="list-style-type: none"> a. Type(s) / Size(s); b. Location(s); c. Mounting Heights; and d. Clearance Requirements. 7. Ceiling: <ol style="list-style-type: none"> a. Height(s); and b. Material(s). 8. Lighting: <ol style="list-style-type: none"> a. Fixture Type(s) / Location(s); and b. Switch / Controls Type(s) / Location(s). 9. Power / Data / Communications: <ol style="list-style-type: none"> a. Outlet Type(s) / Location(s); and b. Mounting Heights. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> • Autocad • TFC Accepted Software Versions |
| Adjacency & Stacking Diagrams | <p>A. Provide 2D and 3D diagrams illustrating horizontal and vertical relationships between spaces and between departments.</p> | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) |

[Return to Table of Contents](#)

* See next page for additional Mobilization / Pre-design Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – MOBILIZATION / PRE-DESIGN (MP1 & MP2) | | (CONTINUED) |
|--|---|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Space Allocation Program | <p>A. Use TFC standard “Space Allocation Program” to report the following for each programmed space:</p> <ol style="list-style-type: none"> 1. Building-wide information: <ol style="list-style-type: none"> a. Building Grossing Factor; b. Total Gross Building Area. 2. Departmental Information: <ol style="list-style-type: none"> a. Using Agency Department Name and ID Number; b. Common Areas; <ol style="list-style-type: none"> i. Circulation Spaces (vertical and Horizontal); ii. Maintenance and Support Spaces: <ol style="list-style-type: none"> (a) Restrooms and Showers; (b) Housekeeping; (c) Shipping and Receiving. iii. Building Service Spaces: <ol style="list-style-type: none"> (a) Mechanical; (b) Electrical; (c) Data / Communications; (d) Plumbing; 3. Space Information: <ol style="list-style-type: none"> a. Space Name and ID Number; b. Space Type; c. Number of occupants; d. Net area and dimensions (length, width, and ceiling height) e. Number Required. f. Total occupancy (number x occupants); g. Total Net Area (number x net area); h. Departmental Grossing Factor; i. Departmental Gross Area (factor x total net); and | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwx) • TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Mobilization / Pre-design Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – MOBILIZATION / PRE-DESIGN (MP1 & MP2) | | (CONTINUED) |
|--|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Narratives / Analyses / Evaluations | <p>A. Provide written analyses, assumptions, and recommendations to be included as the Basis of Design for materials, systems, equipment and energy sources for the following:</p> <ol style="list-style-type: none"> 1. HVAC Systems: <ol style="list-style-type: none"> a. Coordination events schedule; b. Load Estimates (order of magnitude); c. Strategy for resolving conflicts between: <ol style="list-style-type: none"> i. Project criteria; ii. Design / Technical Standards; and iii. Code Requirements. 2. Plumbing Systems: <ol style="list-style-type: none"> a. Domestic and Fire water pressure and line size requirements; b. Wastewater: <ol style="list-style-type: none"> i. Discharge capacity; ii. Lift station requirements (if applicable). 3. Energy Sources: <ol style="list-style-type: none"> a. Primary Utility; b. Emergency / Standby Power; 4. Energy Conservation; <ol style="list-style-type: none"> a. Alternative Energy Sources b. Metering of: <ol style="list-style-type: none"> i. Electrical power and lighting; ii. Natural Gas; iii. Domestic, irrigation, and process water. c. Artificial lighting and daylighting systems and controls strategies; 5. Energy Consumption: <ol style="list-style-type: none"> a. Anticipated total monthly building energy usage. 6. Smoke and emission control systems; 7. Fire and Life Safety systems; 8. Building Management System. <p>B. Estimate above ceiling space requirements for all systems.</p> <p>C. List all materials / systems yet to be determined.</p> | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwx) • TFC Accepted Software Versions |

[Return to Table of Contents](#)

[Abbreviations](#)



| SUBMISSION CONTENT – SCHEMATIC DESIGN (SD1 & SD2) | | |
|---|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| General | A. Describe the proposed conceptual design, scale, and relationships among the major components of the Project. | |
| Executive Summary Report | A. Revise the previous report to reflect current project conditions. | <ul style="list-style-type: none"> · Autodesk Design Review (.dwf or .dwx) · TFC Accepted Software Versions |
| Schedule for Delivery of Services | A. Revise the previous Schedule to reflect any changes to anticipated task durations and milestone dates. | |
| Estimate of Probable Construction Cost | A. Revise the previous Estimate based on <ol style="list-style-type: none"> 1. New information regarding proposed building systems and materials; and 2. Square footage calculations as measured from the SD Drawings: <ol style="list-style-type: none"> a. Basis for Measurement: AIA Document D101 - Methods of Calculating the Area and Volume of Buildings; B. Retain the CSI Uniformat organization; C. Include the same types of contingencies as in the previous phase. | |
| Space Allocation Program | A. Revise the previous Space Allocation Program to reflect new or deleted spaces; and B. Provide square footages: <ol style="list-style-type: none"> 1. Measured from drawings below; 2. Use AIA Document D101 - Methods of Calculating the Area and Volume of Buildings. | |
| BIM Model (When Provided) | A. Provide all BIM model and annotation files (and all linked files) containing all features of the project as indicated in the Drawing requirements below. B. See BIM Standards for more information. | |

[Return to Table of Contents](#)

* See next page for additional Schematic Design Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – SCHEMATIC DESIGN (SD1 & SD2) | | (CONTINUED) |
|---|---|--|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Drawings – SD1 | <p>A. Provide drawings describing the proposed design containing the following:</p> <ol style="list-style-type: none"> 1. Project information; <ol style="list-style-type: none"> a. TFC Project Name and TFC Project Number; b. Project address / Location map; c. Team members; d. Drawing index; e. Submission Milestone. 2. Site: <ol style="list-style-type: none"> a. Existing conditions site survey; b. Property lines, setbacks, easements, and view corridor restrictions (existing and proposed including metes and bounds); c. Building locations; d. Adjacent roadways; e. Site Demolition; f. Public transportation stops; g. Vehicular and pedestrian circulation paths and parking; h. Service vehicle access; i. Landscape planting strategies; j. Basic grading and soil retention strategies; k. Pools, ponds, and other water features; l. Storm water management strategies (as applicable) for: <ol style="list-style-type: none"> i. Rainwater collection; ii. Drainage, Filtration, and Detention. m. Utility service locations and routing (existing and proposed); n. Major exterior equipment locations and sizes such as: <ol style="list-style-type: none"> i. Diesel generators; ii. Electrical enclosures; iii. Communications towers; and iv. Fuel storage facilities. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> • Autocad • TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Schematic Design Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – SCHEMATIC DESIGN (SD1 & SD2) | | (CONTINUED) |
|---|---|--|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| <p>Drawings – SD1 (Continued)</p> | <ol style="list-style-type: none"> 1. Floor Plan(s): <ol style="list-style-type: none"> a. Overall building configuration; b. Arrangement of programmed spaces; c. Space names and numbers coordinated with Space Allocation Program; d. Horizontal and vertical circulation elements; e. Furniture layouts; 2. Roof Plan: <ol style="list-style-type: none"> a. Basic configuration; b. Major slopes defined; 3. Major exterior Building Elevations: <ol style="list-style-type: none"> a. Design vocabulary; b. Basic materials; c. Door and window openings; d. Floor-to-floor heights; e. Line of finished grade. 4. Building Section(s) as needed to illustrate unique volumetric characteristics of the proposed design. 5. MEP: <ol style="list-style-type: none"> a. One Line diagrams; b. Major equipment locations and sizes identified such as: <ol style="list-style-type: none"> i. Chillers; ii. Fire Pump; iii. Emergency Generator; iv. Automatic Transfer Switch (ATS); v. Uninterruptable Power Supply (UPS); and vi. Switchboards and Panels vii. Building Management System (BMS). 6. Other drawings if needed to illustrate important design features. 7. Legends and symbols: All disciplines. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> • Autocad • TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Schematic Design Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – SCHEMATIC DESIGN (SD1 & SD2) | | (CONTINUED) |
|---|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Drawings – SD2 | A. Provide final presentation documents reflecting satisfactory responses to TFC comments regarding the SD1 documents; and B. Renderings: Photo-realistic color perspectives of the exterior of the proposed building(s) in context with their surroundings: <ol style="list-style-type: none"> a. One bird’s-eye” view (or other view as determined by TFC); and b. One eye-level view that includes the main façade. | <ul style="list-style-type: none"> • Renderings: 600 DPI (.png) |
| Specifications | A. List primary materials and building systems: <ol style="list-style-type: none"> 1. Format: Outline using TFC template. B. See appendices for technical standards | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwx) |
| Energy Efficient Architectural and Engineering Design Alternatives Evaluation (HPB – Energy Efficiency – General) | A. Develop in greater detail and verify results of the Energy Efficient Architectural and Engineering Design Alternatives Evaluation provided by TFC at the beginning of the Mobilization and Pre-design Phase. <ol style="list-style-type: none"> 1. Address all requirements of TGC Sections 2166.153, 2166.401, 2166.403, and 2166.408 such as: <ol style="list-style-type: none"> a. Identify and compare the benefits and disadvantages of potential alternatives including: <ol style="list-style-type: none"> i. Environmental impact (both initially and over the project’s life cycle); ii. Economic Impact (both initially and over the project’s life cycle). b. Recommend the best alternatives considering both economic and environmental life-cycle costs and benefits. 2. Determine the viability of accommodating future alternative energy system installations by providing anticipated floor space and service pathways in the current design. B. When using BIM, utilize data embedded in the BIM model in conjunction with other appropriate energy modeling software and web-based weather/energy databases to perform this analysis. <ol style="list-style-type: none"> 1. Modeling shall comply with ASHRAE 90.1 (currently adopted edition) Appendix G Performance Rating Method. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwx) • TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Schematic Design Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – SCHEMATIC DESIGN (SD1 & SD2) | | (CONTINUED) |
|---|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| <p>Narratives / Analyses</p> <p>(HPB – Water Use Efficiency)</p> | <p>A. Recommend the most appropriate assemblies/equipment/systems that address project specific needs including:</p> <ol style="list-style-type: none"> 1. Operating Concepts: Critical ideas behind the recommended design solution and the rationale which supports that solution: <ol style="list-style-type: none"> a. Statutory and regulatory requirements; b. Interrelationships between spaces (both interior and exterior); c. Life safety features; d. Material and building systems selections; e. Artificial Lighting and Daylighting strategies for each type of space; f. Environmental quality (both interior and exterior); g. Emergency operations 2. Water conservation/efficiency (SECO Water Conservation Standard); 3. Foundation and Structural Frame Systems: <ol style="list-style-type: none"> a. Brief analysis of soils report as related to system selection; b. Comparison of benefits and disadvantages of potential systems; 4. Building Envelope: <ol style="list-style-type: none"> a. Brief description of existing and new building envelope assemblies (as applicable); 5. Comparison of the proposed envelope assemblies to the ASHRAE 90.1- (currently adopted edition) Appendix G baseline. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwx) • TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Schematic Design Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – SCHEMATIC DESIGN (SD1 & SD2) | | (CONTINUED) |
|--|---|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| <p>Narratives / Analyses (Continued) (HPB – IEQ – IAQ)</p> | <ol style="list-style-type: none"> 6. Indoor Air Quality and Pollutant Source Control Plan: Include specific strategies for addressing the TFC: <ol style="list-style-type: none"> a. Design Standards – Indoor Air Quality sections; and b. Technical Standards – 01 81 19 - Indoor Air Quality Requirements. 7. MEP, Fire Alarm, Fire Protection, and Security Systems Narratives: <ol style="list-style-type: none"> a. Brief description of existing and new systems/conditions (as applicable); b. List of assumptions and unknowns; c. Design criteria; d. Benefits and disadvantages of potential equipment/systems; e. Comparison of the proposed systems to the ASHRAE 90.1 (currently adopted edition) Appendix G baseline. <ol style="list-style-type: none"> i. Target Efficiency: 15% more efficient than baseline building. ii. Maximum Payback Period: 5 years. f. Address preparation of electrical breaker coordination study and NFPA 70E labeling requirements. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwx) • TFC Accepted Software Versions |

[Return to Table of Contents](#)

[Abbreviations](#)



| SUBMISSION CONTENT – DESIGN DEVELOPMENT (DD1 & DD2) | | |
|---|---|--|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| General | A. Illustrate and coordinate all important aspects of the Project. B. Resolve all major issues that could cause significant restudy during the CD phase. | |
| Executive Summary Report | A. Revise the previous report to reflect current project conditions. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) • TFC Accepted Software Versions |
| Schedule for Delivery of Services | A. Revise the previous Schedule to reflect any changes to anticipated task durations and milestone dates. | |
| Estimate of Probable Project Construction Cost | A. Revise the previous estimate based on: <ol style="list-style-type: none"> 1. New information regarding proposed building systems and materials; and <ol style="list-style-type: none"> a. Quantities take-off as measured from the DD Drawings. B. Retain the CSI Unifomat organization. C. Include the same types of contingencies as in the previous phase. | |
| Space Allocation Program | A. Same as SD submission content above plus the following: <ol style="list-style-type: none"> 1. Add room numbers (from drawings below). | |
| BIM Model (When Provided) | A. Same as SD submission content above plus the following: <ol style="list-style-type: none"> 1. All physical features of the project as indicated in the Drawing requirements below. 2. Prior to document submission, use conflict checking software to: <ol style="list-style-type: none"> a. Identify and resolve clashes between all disciplines and specialties included on the project: <ol style="list-style-type: none"> i. Hard clashes between the various elements; and ii. Soft clashes between any element(s) and required clearances. b. Submit the report generated by the checking software indicating that conflicts have been resolved. | |
| | B. See BIM Standards for more information. | |

[Return to Table of Contents](#)

* See next page for additional Design Development Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – DESIGN DEVELOPMENT (DD1 & DD2) | | (CONTINUED) |
|---|---|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Drawings - DD1 | <p>A. Same as SD submission content above plus the following:</p> <ol style="list-style-type: none"> 1. Site: <ol style="list-style-type: none"> a. Accessible Route; b. Landscape planting and irrigation plans; c. Site furnishings and appurtenances; d. Planter, wall, and fence elevations; e. Grading Plan (with critical spot elevations); f. Utility Plan; g. Typical details; <ol style="list-style-type: none"> i. Planting; ii. Paving and hardscape; iii. Retaining walls and planters; iv. Bollards; v. Utilities. h. Parking counts; 2. Floor Plan(s): <ol style="list-style-type: none"> a. Room and door numbers; b. Reference keys: <ol style="list-style-type: none"> i. Enlarged plans; ii. Partition types; iii. Exterior and Interior elevations; iv. Building and Wall sections; and v. Plan details. c. Dimensions: <ol style="list-style-type: none"> i. Massing; ii. Structural Grid; and iii. Partitions. d. Furniture layouts. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwt) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> • Autocad • TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Design Development Submission Content.

[Abbreviations](#)



SUBMISSION CONTENT – DESIGN DEVELOPMENT (DD1 & DD2) (CONTINUED)

| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
|--|---|--|
| <p>Drawings - DD1 (Continued)</p> | <ol style="list-style-type: none"> 1. Roof: <ol style="list-style-type: none"> a. All slopes indicated; b. Major equipment locations identified; c. Major MEP penetrations coordinated; d. Reference keys: <ol style="list-style-type: none"> i. Building and Wall sections. 2. Exterior Building Elevations: <ol style="list-style-type: none"> a. All building faces; b. Material patterns; c. Vertical dimensions; d. Structural grid; e. Building section and wall section keys; f. Major MEP penetrations coordinated. 3. Detailed code compliance information (all disciplines); <ol style="list-style-type: none"> a. Reference codes; b. Jurisdictional authorities; c. Building information: <ol style="list-style-type: none"> i. Construction type; ii. Occupancy(ies); iii. Fire suppression systems; d. Code compliance calculations indicating both allowable/required and proposed conditions: <ol style="list-style-type: none"> i. Height and area; ii. Exiting; iii. Plumbing fixture count; e. Life safety plans: <ol style="list-style-type: none"> i. Occupant loading; ii. Exiting; iii. Fire rated walls and partitions clearly identified. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwt) <li style="text-align: center;">AND • Autocad • TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Design Development Submission Content.

[Abbreviations](#)



SUBMISSION CONTENT – DESIGN DEVELOPMENT (DD1 & DD2) (CONTINUED)

| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
|--|---|--|
| <p>Drawings - DD1 (Continued)</p> | <ol style="list-style-type: none"> 1. Enlarged floor plans; <ol style="list-style-type: none"> a. Typical room layouts (as applicable to project type); b. Restrooms / Showers; c. Stairs, ramps, and elevators; and d. Other specialty spaces as appropriate to the proposed design. 2. Interior / Millwork Elevations; 3. Door and frame information: <ol style="list-style-type: none"> a. Schedule (including hardware set assignments); b. Types; and c. Typical head, jamb, and sill details. 4. Hardware Schedule: <ol style="list-style-type: none"> a. Generic functions only; b. Basis of Design: Include in specifications. 5. Room Finish Schedule (by individual space); 6. Reflected Ceiling Plans; 7. Architectural Details (typical); 8. Structural: <ol style="list-style-type: none"> a. Foundation and Framing Plans; b. Loading assumptions and member sizes; c. Important details. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> • Autocad • TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Design Development Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – DESIGN DEVELOPMENT (DD1 & DD2) | | (CONTINUED) |
|---|---|--|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Drawings – DD2 | A. Provide drawings describing the proposed design containing the following: <ol style="list-style-type: none"> 1. Detailed code compliance information; 2. Metering: <ol style="list-style-type: none"> a. Meter locations; b. Types of data being metered. 3. Mechanical: <ol style="list-style-type: none"> a. Site information (if applicable); b. Equipment and thermostat locations; c. Primary distribution routing and sizes; d. Secondary distribution routing; e. Supply devices with CFM; f. Riser diagrams; g. Major duct penetrations (Locations and sizes); and h. Equipment selections / Schedules. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> • Autocad • TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Design Development Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – DESIGN DEVELOPMENT (DD1 & DD2) | | (CONTINUED) |
|---|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Drawings – DD2 (Continued) | 4. Electrical: <ul style="list-style-type: none"> a. Site information (if applicable); b. Equipment locations; c. Floor Plans: <ul style="list-style-type: none"> i. Lighting layout; ii. Lighting Footcandle Levels (interior and exterior) including tables showing: <ul style="list-style-type: none"> (a) Maximum, average, and minimum lighting levels; (b) Maximum-to-Average ratio; (c) Average-to-Minimum ratio. iii. Power (panel and receptacle locations); iv. Lightning Protection and Grounding; v. Data / Communications (indicating drop locations); vi. Fire Alarm (FACP and device locations); vii. Security Systems (access control, CCTV, equipment schedules). d. Riser diagrams: <ul style="list-style-type: none"> i. Expected panels and transformers; ii. Cable and conduit information. e. Equipment and Fixture Schedules; f. Lighting Density Schedule for main areas: Demonstrate compliance with ASHRAE 90.1-(Currently adopted edition). 5. Plumbing and Fire Protection: <ul style="list-style-type: none"> a. Site information (if applicable); b. Equipment and fixture locations; <ul style="list-style-type: none"> i. Supply, waste, vent, and storm routing with flow rate quantities. c. Riser diagrams; d. Major piping penetrations and risers (Locations and sizes); and B. Equipment and Fixture Schedules. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwt) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> • Autocad • TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Design Development Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – DESIGN DEVELOPMENT (DD1 & DD2) | | (CONTINUED) |
|---|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Specifications | A. Describe primary materials and building systems. <ol style="list-style-type: none"> 1. Format: Short form using TFC template. 2. Copies of manufacturers' data and/or illustrations of materials and equipment proposed to be specified for the Project. B. See appendices for technical standards. C. Manufacturers' Data Sheets: <ol style="list-style-type: none"> 1. Lighting Fixtures; 2. Lighting Controls; 3. Lamps (identify proposed lamp temperatures) | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwx) • TFC Accepted Software Versions |
| Narratives / Analyses / Evaluations | A. Revise narratives and analyses submitted in the previous phase: <ol style="list-style-type: none"> 1. Summarize decisions made (and supporting reasons) for each. B. Identify possible impacts of Construction phasing on Design strategies. | |
| Data / Calculations | A. Provide data and calculations for the following: <ol style="list-style-type: none"> 1. Building Envelope Comcheck confirming compliance with ASHRAE 90.1 (currently adopted edition). 2. MEP Equipment List: <ol style="list-style-type: none"> a. Location(s), Size(s), and Weight(s); b. Clearance requirements. 3. Mechanical: <ol style="list-style-type: none"> a. Load analysis summary; b. Building pressure air quantity summary: <ol style="list-style-type: none"> i. Exhaust; ii. Outside Air; iii. Required occupant ventilation. c. Sequence of operations for major equipment and BMS criteria; d. Electrical Load analysis summary (include schedules documenting the sizing of the system / equipment). e. Lighting Comcheck confirming compliance with ASHRAE 90.1. 4. Plumbing and Fire Protection: Flow test (capacity and pressure). | |

[Return to Table of Contents](#)

[Abbreviations](#)



| SUBMISSION CONTENT – CONTRACT DOCUMENTS (CD1 & CD2) | | |
|---|--|--|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| General | A. Develop detailed and coordinated documents setting forth the requirements for the construction of the project. | |
| Executive Summary Report | A. Revise the previous report to reflect current project conditions. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) • TFC Accepted Software Versions |
| Schedule for Delivery of Services | A. Revise the previous Schedule to reflect any changes to anticipated task durations and milestone dates. | |
| Estimate of Probable Project Construction Cost | A. Revise the previous estimate based on: <ol style="list-style-type: none"> 1. New information regarding proposed building systems and materials; and 2. Detailed quantities take-off (measured from Drawings below). B. Change to the CSI MasterFormat 2004/2011 format; C. Include the same types of contingencies as in the previous phase. | |
| Space Allocation Program | A. Same as DD submission content above. | |
| BIM Model (When Provided) | A. Same as DD submission content above ; and B. All physical features of the project as indicated in the Drawing requirements below. C. See BIM Standards for more information. | <ul style="list-style-type: none"> • Autodesk Navisworks (.nwd and all linked .nwf files) • Autodesk Civil3D • Autodesk Revit |

[Return to Table of Contents](#)

* See next page for additional Contract Document Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – CONTRACT DOCUMENTS | | (CONTINUED) |
|---|---|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Drawings | <p>A. Same as DD submission content above plus the following:</p> <ol style="list-style-type: none"> 1. Site: <ol style="list-style-type: none"> a. Erosion and Sedimentation Control (plan and details); b. Fire Protection Plan; c. Accessible Signage; d. Dimensions; e. Additional detailing as appropriate for the project needs; f. Grading Plan (with all spot elevations); g. Landscape planting and irrigation details; h. Impervious cover calculations; and i. Utility profiles. 2. Floor Plan(s): <ol style="list-style-type: none"> a. Dimensions (all); and b. Furniture layouts moved to Furniture Plans (for reference only). 3. Roof: <ol style="list-style-type: none"> a. All equipment and walk pad locations; b. Safety tie-backs (if applicable); and c. Detail reference keys. 4. Architectural Details (all); 5. Structural: All remaining notes, plans, schedules, and details; 6. Mechanical: <ol style="list-style-type: none"> a. Equipment and fan room layouts; b. All ductwork routing and sizes; c. Fire and smoke dampers; d. Equipment Schedules; e. Flow and control diagrams; f. All remaining drawings, notes, schedules, and details. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> • Autocad 2010 • TFC Accepted Software Versions |

[Return to Table of Contents](#)

* See next page for additional Contract Document Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – CONTRACT DOCUMENTS | | (CONTINUED) |
|---|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Drawings (Continued) | 1. Electrical / Fire Alarm: <ul style="list-style-type: none"> a. Electrical details showing such things as: <ul style="list-style-type: none"> i. Grounding; ii. ATS; iii. Wiring; iv. Lightning protection; v. Fencing; and vi. Housekeeping pads. b. All remaining notes, plans, schedules, and details. 2. Plumbing / Fire Protection: <ul style="list-style-type: none"> a. Equipment and pump room layouts; b. All piping routing and sizes; c. Fixture and Equipment Schedules; d. Flow and riser diagrams; e. Fire sprinkler hazard zones; f. Fire hydrant static and residual pressures: <ul style="list-style-type: none"> i. Indicate fire and / or domestic water pump requirements. B. All remaining notes, plans, schedules, and details. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> • Autocad 2010 • TFC Accepted Software Versions |
| Specifications | A. Provide complete Project Manual: <ul style="list-style-type: none"> 1. Format: 3 part CSI MasterFormat 2004/2011. 2. Include all TFC Front-End documents as provided by TFC’s PM. 3. Include the following TFC-provided matrices at the end of the Project Close Out section of the Project Manual and complete them to reflect project specific requirements: <ul style="list-style-type: none"> a. Submittals; b. Warranties; c. Testing; d. Training; and e. Manuals. B. See the Appendices for relevant technical standards. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) |

[Return to Table of Contents](#)

* See next page for additional Contract Document Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – CONTRACT DOCUMENTS | | (CONTINUED) |
|--|---|--|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Narratives / Analyses / Evaluations | A. Revise narratives and analyses submitted in the previous phase: <ol style="list-style-type: none"> 1. Summarize decisions made (and supporting reasons) for each. B. Update the DD MEP systems narratives to indicate intended operational and maintenance procedures (for building occupants). <ol style="list-style-type: none"> 1. Address requirements of ASHRAE Standard 180 - Standard Practice for Inspection and Maintenance of Commercial Building HVAC Systems. C. Estimate to what extent structural, building envelope, & hardscape materials need to be replaced or repaired. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) • TFC Accepted Software Versions |
| Data / Calculations | A. Same as DD submission content above indicate the following: <ol style="list-style-type: none"> 1. Room by room electrical load analysis per ASHRAE 90.1 (currently adopted edition); 2. Changes from previous submission; 3. Duct and piping calculations; 4. Air balance calculations; 5. Energy and ventilation calculations. | |

[Return to Table of Contents](#)

[Abbreviations](#)



| SUBMISSION CONTENT – CONTRACT BIDDING AND AWARD (BA) | | |
|--|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| General | A. Execute and issue bid documents that form the basis of competitive price proposals. | |
| Executive Summary Report | A. Revise the previous report to reflect current project conditions. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) • TFC Accepted Software Versions |
| Schedule for Delivery of Services | A. Revise the previous Schedule to reflect any changes to anticipated task durations and milestone dates. | |
| Space Allocation Program | A. Same as DD submission content above. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) |
| Bid Documents | A. Provide final, executed (sealed and signed): <ol style="list-style-type: none"> 1. Drawings and Specifications reflecting satisfactory responses to TFC comments; and 2. Addenda and Clarifications as required to sufficiently respond to: <ol style="list-style-type: none"> a. Requirements of regulatory authorities; b. Bidder Requests for Information; and c. Requests for Substitution. | <ul style="list-style-type: none"> • Autodesk Design Review (.dwf or .dwfx) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> • Autocad 2010 |
| BIM Models (When Provided) | A. Provide all BIM model and annotation files (and all linked files) reflecting the information contained within the Bid Documents as described below. B. See BIM Standards for more information. | <ul style="list-style-type: none"> • Autodesk Navisworks (.nwd and .nwf files) • Autodesk Civil3D • Autodesk Revit |
| Narratives / Analyses / Evaluations | A. Revise narratives and analyses submitted in the previous phase: <ol style="list-style-type: none"> 1. Summarize decisions made (and supporting reasons) for each. | |

[Return to Table of Contents](#)

* See next page for additional Contract Bidding and Award Submission Content.

[Abbreviations](#)



| SUBMISSION CONTENT – CONTRACT BIDDING AND AWARD (BA) | | (CONTINUED) |
|--|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Data / Calculations | A. Same as CD submission content above. | |
| SECO Documentation | A. Submit sealed and executed SECO compliance forms and supporting documentation in accordance with SECO requirements and the Submission Procedures section of this document. | |
| Accessibility Review | A. Register project and submit documentation to TDLR or a RAS in accordance with the TDLR requirements and the Submission Procedures section of this document. | |
| Hazardous Materials Certification | A. Submit letter (complying with the hazardous materials statutory requirements listed above) certifying that the project and all parts of any building(s) affected by the project do not contain asbestos. | · Adobe PDF |
| TCEQ / EPA Documentation | A. Submit: <ol style="list-style-type: none"> 1. SWPPP complying with TAC Title 30, Part 1, Chapter 213, Subchapter B, RULE §213.24. 2. SPCC Plan (EPA) for fuel storage tanks; 3. Fuel storage tank registration (TCEQ). | · <u>As required by TCEQ and/or EPA</u> |

[Return to Table of Contents](#)

[Abbreviations](#)



| SUBMISSION CONTENT – CONSTRUCTION (CA) | | |
|---|---|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Schedule for Delivery of Services | A. Revise the previous Schedule to reflect any changes to anticipated task durations and milestone dates. | <ul style="list-style-type: none"> Autodesk Design Review (.dwf or .dwfx) |
| Consolidated Contract Documents | A. Provide final, executed (sealed and signed) Drawings and Specifications updated to reflect all revisions including Addenda and Clarifications issued during the Contract Bidding and Award phase. | <ul style="list-style-type: none"> Autodesk Design Review (.dwf or .dwfx) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> Autocad 2010 |
| BIM Model and Annotation Files (When Provided) | <p>A. Provide all BIM model and annotation files (and all linked files) reflecting the information contained within the Consolidated Contract Documents as described above;</p> <p>B. See BIM Standards for more information.</p> | <ul style="list-style-type: none"> Autodesk Navisworks (.nwd and .nwf files) Autodesk Civil3D Autodesk Revit |
| Change Documentation | <p>A. Provide final, executed (sealed and signed) Change Documentation including Drawings and Specifications reflecting agreed upon changes to the Contract for Construction such as:</p> <ol style="list-style-type: none"> 1. Minor Changes / Supplemental Instructions (UGC 11.4) such as those resulting from: <ol style="list-style-type: none"> a. Modifications to shop drawings and other submittals; b. RFI responses. 2. Changes resulting from unforeseen concealed conditions (UGC 11.5); and 3. Change Orders. | <ul style="list-style-type: none"> Autodesk Design Review (.dwf or .dwfx) TFC Accepted Software Versions |

[Return to Table of Contents](#)

[Abbreviations](#)



| SUBMISSION CONTENT – WARRANTY | | |
|--|--|---|
| DOCUMENT | PSP ACTIONS REQUIRED | ELECTRONIC SUBMISSION FILE FORMAT |
| Record Documents | A. Update Drawings and specifications to reflect the “as-constructed” condition of the complete scope of the project as recorded in Contractor’s as-constructed field marked Record Documents and all: <ol style="list-style-type: none"> 1. Addenda; 2. Clarifications; 3. Minor Changes / Supplemental Instructions (UGC 11.4) such as those resulting from: <ol style="list-style-type: none"> a. Modifications to shop drawings and other submittals; b. RFI responses. 4. Changes resulting from unforeseen concealed conditions (UGC 11.5); 5. Change Orders; and 6. Product, material, and equipment substitutions. B. Finalize the MEP Systems Operations Manual. <ol style="list-style-type: none"> 1. Comply with ASHRAE Guideline 0, Informative Annex O. | <ul style="list-style-type: none"> · Autodesk Design Review (.dwf or .dwfx) <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> · Autocad 2010 <p style="text-align: center;">AND</p> <ul style="list-style-type: none"> · Microsoft Word 2007 · TFC Accepted Software Versions |
| Record BIM Models (When Provided) | A. Update all BIM model and annotation files (and all linked files) to reflect the information contained within the Record Documents as described above. B. Tag all components in the BIM models with embedded hyperlinks to the relevant: <ol style="list-style-type: none"> 1. Specification section in the Project Manual; 2. Product / Equipment Information in the O&M Manual; 3. Final, accepted Submittal Data; 4. Training Materials; 5. Commissioning Documentation; 6. Systems Manuals; and 7. Warranty Documents. C. See BIM Standards for more information. | <ul style="list-style-type: none"> · Autodesk Navisworks (.nwd and .nwf files) · Autodesk Civil3D · Autodesk Revit |

[Return to Table of Contents](#)

[Abbreviations](#)



DRAWING STANDARDS – RECOMMENDED DOCUMENT ORGANIZATION

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--------------------------|--|-----------------------|--------|---------------|-------------|--|--------------------|------------------|----------|------------------|---|-------------------------|-----------|----------|--|---|---|---|--|--|---|---|---|--|--|---|---|---|--|
| Purpose | A. Facilitate familiarity of the document structure and contents by all parties. B. Deviations from the recommended document organization standards (when appropriate) must receive prior written approval from TFC’s PM. | | | | | Drawing Numbering A. Begin numbering in the bottom right corner. B. Continue numbering upward and then to the left. | | | | | <table border="1"> <tr> <td></td> <td>9</td> <td>6</td> <td>3</td> <td></td> </tr> <tr> <td></td> <td>8</td> <td>5</td> <td>2</td> <td></td> </tr> <tr> <td></td> <td>7</td> <td>4</td> <td>1</td> <td></td> </tr> </table> | | | | | 9 | 6 | 3 | | | 8 | 5 | 2 | | | 7 | 4 | 1 | |
| | | 9 | 6 | 3 | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 8 | 5 | 2 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | 7 | 4 | 1 | | | | | | | | | | | | | | | | | | | | | | | | | | |
| DESIGN DISCIPLINE | General (Notes, Abbreviations, and Symbols) | Existing / Demolition | PLANS | | | ELEVATIONS | | | SECTIONS | | | | SCHEDULES | DIAGRAMS | | | | | | | | | | | | | | | |
| | | | Plan | Enlarged Plan | Plan Detail | Elevation | Enlarged Elevation | Elevation Detail | Section | Enlarged Section | Section Detail | Enlarged Section Detail | | | | | | | | | | | | | | | | | |
| | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | | | | | | | | | | | | | | | |
| Cover | G0-00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Project Information | G0-01 | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Accessibility | AR-01... | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Code Review | CR-01... | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| General Notes | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Civil | C0-00 | C1-100 | C2-100 | C3-100 | C4-100 | | | | C8-100 | | | | C12-100 | C13-100 | | | | | | | | | | | | | | | |
| Dimension Control | | C1-200 | C2-200 | C3-200 | C4-200 | | | | C8-200 | | | | C12-200 | C13-200 | | | | | | | | | | | | | | | |
| Erosion / Sedimentation | | C1-300 | C2-300 | C3-300 | C4-300 | | | | C8-300 | | | | C12-300 | C13-300 | | | | | | | | | | | | | | | |
| Grading | | C1-400 | C2-400 | C3-400 | C4-400 | | | | C8-400 | | | | C12-400 | C13-400 | | | | | | | | | | | | | | | |
| Storm Water | | C1-500 | C2-500 | C3-500 | C4-500 | | | | C8-500 | | | | C12-500 | C13-500 | | | | | | | | | | | | | | | |
| Utilities | | C1-600 | C2-600 | C3-600 | C4-600 | | | | C8-600 | | | | C12-600 | C13-600 | | | | | | | | | | | | | | | |
| Landscape | L0-000 | L1-100 | L2-100 | L3-100 | L4-100 | L5-100 | L6-100 | L7-100 | L8-100 | L9-100 | L10-100 | L11-100 | L12-100 | | | | | | | | | | | | | | | | |
| Hardscape | | L1-200 | L2-200 | L3-200 | L4-200 | L5-200 | L6-200 | L7-200 | L8-200 | L9-200 | L10-200 | L11-200 | L12-200 | L13-200 | | | | | | | | | | | | | | | |
| Planting | | L1-300 | L2-300 | L3-300 | L4-300 | | | | L8-300 | L9-300 | L10-300 | L11-300 | L12-300 | L13-300 | | | | | | | | | | | | | | | |
| Irrigation | | L1-400 | L2-400 | L3-400 | L4-400 | | | | L8-400 | L9-400 | L10-400 | L11-400 | L12-400 | L13-400 | | | | | | | | | | | | | | | |
| Structural | S0-000 | S1-100 | S2-100 | S3-100 | S4-100 | S5-100 | S6-100 | S7-100 | S8-100 | S9-100 | S10-100 | S11-100 | S12-100 | S13-100 | | | | | | | | | | | | | | | |
| Architecture | A0-000 | A1-100 | A2-100 | A3-100 | A4-100 | A5-100 | A6-100 | A7-100 | A8-100 | A9-100 | A10-100 | A11-100 | A12-100 | | | | | | | | | | | | | | | | |
| Site | | A1-200 | A2-200 | A3-200 | A4-200 | A5-200 | A6-200 | A7-200 | A8-200 | A9-200 | A10-200 | A11-200 | A12-200 | | | | | | | | | | | | | | | | |
| Floor / Roof | | A1-300 | A2-300 | A3-300 | A4-300 | A5-300 | A6-300 | A7-300 | A8-300 | A9-300 | A10-300 | A11-300 | A12-300 | | | | | | | | | | | | | | | | |
| Openings | | | | | | | | | | | | | A12-400 | | | | | | | | | | | | | | | | |
| Ceiling | | A1-500 | A2-500 | A3-500 | A4-500 | A5-500 | A6-500 | A7-500 | A8-500 | A9-500 | A10-500 | A11-500 | A12-500 | | | | | | | | | | | | | | | | |
| Wall | | A1-600 | A2-600 | A3-600 | A4-600 | A5-600 | A6-600 | A7-600 | A8-600 | A9-600 | A10-600 | A11-600 | A12-600 | | | | | | | | | | | | | | | | |

[Return to Table of Contents](#)

* See next page for additional Recommended Document Organization Standards.

[Abbreviations](#)



RECOMMENDED DRAWING STANDARDS – DOCUMENT ORGANIZATION (CONTINUED)

| DESIGN DISCIPLINE | General (Notes, Abbreviations, and Symbols) | Existing / Demolition | PLANS | | | ELEVATIONS | | | SECTIONS | | | | SCHEDULES | DIAGRAMS |
|-------------------------------|---|-----------------------|---------|---------------|-------------|------------|--------------------|------------------|----------|------------------|----------------|-------------------------|-----------|----------|
| | | | Plan | Enlarged Plan | Plan Detail | Elevation | Enlarged Elevation | Elevation Detail | Section | Enlarged Section | Section Detail | Enlarged Section Detail | | |
| | | | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | | |
| Interior | I0-000 | I1-100 | I2-100 | I3-100 | I4-100 | I5-100 | I6-100 | I7-100 | I8-100 | I9-100 | I10-100 | I11-100 | I12-100 | |
| Floor | | I1-200 | I2-200 | I3-200 | I4-200 | I5-200 | I6-200 | I7-200 | I8-200 | I9-200 | I10-200 | I11-200 | I12-200 | |
| Ceiling | | I1-300 | I2-300 | I3-300 | I4-300 | I5-300 | I6-300 | I7-300 | I8-300 | I9-300 | I10-300 | I11-300 | I12-300 | |
| Wall | | I1-400 | I2-400 | I3-400 | I4-400 | I5-400 | I6-400 | I7-400 | I8-400 | I9-400 | I10-400 | I11-400 | I12-400 | |
| Casework | | I1-500 | I2-500 | I3-500 | I4-500 | I5-500 | I6-500 | I7-500 | I8-500 | I9-500 | I10-500 | I11-500 | I12-500 | |
| Finishes | | I1-600 | I2-600 | I3-600 | | | | | | | | | I12-600 | |
| Furniture | | I1-700 | I2-700 | I3-700 | I4-700 | I5-700 | I6-700 | I7-700 | I8-700 | I9-700 | I10-700 | I11-700 | I12-700 | |
| Signage | | I1-800 | I2-800 | I3-800 | I4-800 | I5-800 | I6-800 | I7-800 | I8-800 | I9-800 | I10-800 | I11-800 | I12-800 | |
| Mechanical | M0-000 | M1-100 | M2-100 | M3-100 | M4-100 | | | | M8-100 | | | | M12-100 | M13-100 |
| Piping | | M1-200 | M2-200 | M3-200 | M4-200 | | | | M8-200 | | | | M12-200 | M13-200 |
| Building Automation & Control | BA-000 | BA1-100 | BA2-100 | BA3-100 | BA4-100 | | | | BA8-100 | | | | BA12-100 | BA13-100 |
| Electrical | E0-000 | E1-100 | E2-100 | E3-100 | E4-100 | | | | E8-100 | | | | E12-100 | E13-100 |
| Power | | E1-200 | E2-200 | E3-200 | E4-200 | | | | E8-200 | | | | E12-200 | E13-200 |
| Lighting | | E1-300 | E2-300 | E3-300 | E4-300 | | | | E8-300 | | | | E12-300 | E13-300 |
| Fire Alarm | | E1-400 | E2-400 | E3-400 | E4-400 | | | | E8-400 | | | | E12-400 | E13-400 |
| Mechanical | | E1-500 | E2-500 | E3-500 | E4-500 | | | | E8-500 | | | | E12-500 | E13-500 |
| Tele/Data | TD0-000 | TD1-100 | TD2-100 | TD3-100 | TD4-100 | | | | TD8-100 | TD9-100 | TD10-100 | TD11-100 | TD12-100 | TD13-100 |
| Security | SC-000 | SC1-100 | SC2-100 | SC3-100 | SC4-100 | SC5-100 | | | SC8-100 | | | | SC12-100 | SC13-100 |
| Plumbing | P0-000 | P1-100 | P2-100 | P3-100 | P4-100 | | | | P8-100 | | | | P12-100 | P13-100 |
| Fire Protection | FP0-000 | FP1-100 | FP2-100 | FP3-100 | FP4-100 | | | | FP8-100 | | | | FP12-100 | FP13-100 |
| Food Service | FS0-000 | FS1-100 | FS2-100 | FS3-100 | FS4-100 | FS5-100 | FS6-100 | FS7-100 | FS8-100 | FS9-100 | FS10-100 | FS11-100 | FS12-100 | FS13-100 |
| Other | ??0-000 | ??1-100 | ??2-100 | ??3-100 | ??4-100 | ??5-100 | ??6-100 | ??7-100 | ??8-100 | ??9-100 | ??10-100 | ??11-100 | ??12-100 | ??13-100 |

[Return to Table of Contents](#)

[Abbreviations](#)



| CADD / BIM STANDARDS – OVERVIEW | | |
|---------------------------------|--|---|
| | | LINKS |
| General | A. TFC has established CADD software as a means for producing the design and documentation for all projects developed under TFC authority. B. Building Information Modeling (BIM) software may be used in lieu of CADD for any project developed under TFC authority. | <ul style="list-style-type: none"> • CADD Standards • BIM Standards |
| Purpose | A. Facilitate implementation of TFC standards; B. Minimize document review turn-around time through standardization of: <ol style="list-style-type: none"> 1. Elements common to all TFC projects: 2. Format and organization of documents. C. Streamline TFC facilities management and maintenance processes from the date of occupancy through the life of the property. | |
| Software Requirements | A. All CADD files (and BIM Model files when provided) are required to be created using CADD or BIM authoring software in native file formats readable by the current software versions in use by TFC as indicated below: <ol style="list-style-type: none"> 1. Autodesk Autocad 2013 2. Autodesk Civil 3D 2013 3. Autodesk Navisworks 2013 4. Autodesk Revit Architecture 2013 5. Autodesk Revit MEP 2013 6. Autodesk Revit Structure 2013 B. PSPs are responsible for providing proper software training for their staff members assigned to TFC projects. | <ul style="list-style-type: none"> • Autocad • Civil 3D • Navisworks • Revit Architecture • Revit MEP • Revit Structure |

[Return to Table of Contents](#)

[Abbreviations](#)



| CADD STANDARDS | | |
|----------------------------------|---|--------------|
| STANDARD | DESCRIPTION | LINKS |
| Purpose | A. Provide a uniform format for CADD based projects developed under TFC authority. | |
| Template Files | A. The following standard files will be provided by TFC: 1. Cover Sheet; 2. Project Information Sheet; 3. Partition Types and Details; and 4. Blank titleblock. | |
| Existing Conditions Files | A. In cases of facility renovation projects, a copy of the existing CADD drawing files and associated Record Documentation will be made available for download through the project's IMPACT folder structure. B. These files and documents shall be utilized in the preparation of all related design and contract documents. | |
| Accuracy | A. All CAD drawings shall be drafted using precision input employing the most accurate source material available. B. For all drawing entities, zero tolerance is required: 1. All lines meet at intersections; 2. Straight lines are straight; 3. Blocks are inserted properly without overlap; 4. Closure of all polygons, etc. | |

[Return to Table of Contents](#)

* See next page for additional CADD Standards.

[Abbreviations](#)



| CADD STANDARDS | | (CONTINUED) |
|---|---|-------------|
| STANDARD | DESCRIPTION | LINKS |
| Color | <ul style="list-style-type: none"> A. Color will be used to control pen assignments and line weights. B. Select layer colors in accordance with the "Pen / Color Values Table". C. Create all objects with color bylayer. | |
| Linetypes | <ul style="list-style-type: none"> A. Use only standard linetypes. B. Contour lines, dashed lines and other fonted lines shall be made of one continuous line segment, not a series of separate line segments. C. A sample drawing must be submitted and approved by the CAD Manager if multilines are used. | |
| Units | <ul style="list-style-type: none"> A. Set DDUNITS to architectural and angles to deg/min/sec with the precision set at 1/16" | |
| Blocks | <ul style="list-style-type: none"> A. Any graphic entity that occurs repeatedly in drawings should be made into a block. B. Insertion points for blocks shall be consistent with its placement in the drawing <ul style="list-style-type: none"> 1. Keep names simple and descriptive. 2. Use a logical insertion point (center of circle, bottom left corner of object). 3. Blocks must be drawn on layer 0 and inserted on the proper layer; or drawn on the proper layer/ layers and inserted on layer 0. C. Nested blocks are permitted but should be avoided whenever possible. D. If custom nested blocks are used, TFC's CADD Manager must approve them. | |
| External Reference Files (XRefs) | <ul style="list-style-type: none"> A. Bind (do not insert) all reference files into the active file. | |
| Scale | <ul style="list-style-type: none"> A. All model space files must be drawn at real size (1-to-1). B. Objects must be created at full size: <ul style="list-style-type: none"> 1. A 50-foot wall must be drawn to 50 feet 0"; and 2. A 48-inch column must be drawn to 48 inches. C. CAD files will be drawn in 2D only (not 3D). | |

[Return to Table of Contents](#)

* See next page for additional CADD Standards.

[Abbreviations](#)



| CADD STANDARDS | | (CONTINUED) |
|-----------------------|---|-------------|
| STANDARD | DESCRIPTION | LINKS |
| Text and Fonts | <ul style="list-style-type: none"> A. Use only standard text fonts supplied with AutoCAD’s font library. B. Fonts for lettering shall be readable and plottable by AutoCAD with no additional software required. C. Text size must be legible and appropriate to the graphic information presented and the intended plotted scale of the drawing. | |
| Drawing Origin | <ul style="list-style-type: none"> A. The lower left corner of the building shall be placed at 0,0,0. B. For non-rectilinear buildings a logical origin point shall be established. C. The origin point must remain consistent between all model files for the purpose of xref coordination. D. Once the origin is established, it may not be changed. | |
| Dimensions | <ul style="list-style-type: none"> A. All dimensioning shall be associative. <ul style="list-style-type: none"> 1. Break lines and parts of cut-through views are an exception. B. Preferred dimension styles are provided in the template file. | |
| Hatching | <ul style="list-style-type: none"> A. Use pattern hatching sparingly since the practice significantly increases the AutoCAD entity count of a drawing. B. Associative hatching may be used only with the approval of TFC’s CAD Manager. C. Use the solid command or polyline command to represent solid-filled regions when possible. | |
| Layers | <ul style="list-style-type: none"> A. CADD drawings shall be organized in accordance with the TFC Layering Guidelines. <ul style="list-style-type: none"> 1. If the TFC format does not include an appropriate layer name, layer names shall be in accordance with CAD Layer Guidelines as published by the American Institute of Architects (A.I.A.). B. The layer names shall be the long format and shall include the modifier. C. As these layer guidelines allow flexibility in the assignment of layers, a Layer Matrix shall be provided to TFC with the Record Documents. D. All third party add on application packages which modify or create CAD layers or other entities must comply with the AIA CAD Layer Guidelines. | |

[Return to Table of Contents](#)

* See next page for additional CADD Standards.

[Abbreviations](#)



| CADD STANDARDS | | (CONTINUED) |
|--------------------------|---|-------------|
| STANDARD | DESCRIPTION | LINKS |
| Area Calculations | A. Include the following area calculations using area polylines included in the “as-built” submittal. <ol style="list-style-type: none"> 1. Construction Area – Area calculation boundary line will be drawn around the exterior Floor Plan for each level of building on layer a-area-cons 2. Gross Area - Area calculation boundary line will be drawn around interior Floor Plan for each level of building on layer a-area-gros 3. Room Area - Area calculation boundary line will be drawn around each room from the centerline of the wall on layer a-area-room B. Wall edges, partition centerlines and structural centerlines used for area polygons, should be saved in the layers listed above, as appropriate. | |
| Quality Check | A. Check the CADD files to verify the following: <ol style="list-style-type: none"> 1. All entities are: <ol style="list-style-type: none"> a. Dimensionally accurate; b. Inserted on the proper layer; 2. Column and grid line dimensions are correct; 3. Entity intersections meet each other properly; 4. Entities outside the drawing limits are deleted. 5. Colors and linetypes are assigned BYLAYER; 6. Layering system conforms to TFC and AIA CAD Layer Standard. B. Correct any non-compliant conditions. C. Confirm that all files are free of viruses. | |
| Purge / Audit | A. If the drawing file becomes too large, response to commands will be slow and regeneration times will be longer. B. Prior to submitting files: <ol style="list-style-type: none"> 1. Purge all unused blocks, linetypes and layers. 2. Audit all files and “Fix All Errors”. | |

[Return to Table of Contents](#)

[Abbreviations](#)



| BIM STANDARDS – FILE TYPES | | |
|-------------------------------------|--|-------|
| FILE TYPE | DEFINITION | LINKS |
| General | <p>A. There are two types of files for a TFC project:</p> <ol style="list-style-type: none"> 1. Model Files contain all physical features of the project; <ol style="list-style-type: none"> a. Site Models; and b. Building Models. c. All model files shall include: <ol style="list-style-type: none"> i. Existing conditions to remain; ii. Existing conditions to be removed; iii. Proposed new construction; and iv. All elements tagged with CSI Unifomat Level 4 categories; d. The extent of existing conditions modeling required beyond the affected areas and the level of information to be included will be determined based on project-specific needs. 2. Annotation Files: Contain all non-physical information (such as notes, dimensions, details, etc.) describing the physical features contained in the model files. 3. All drawings and schedules required for assessment, review, bidding and construction shall be extractions from the model file(s). <p>B. Separating the project into model and annotation files is intended to:</p> <ol style="list-style-type: none"> 1. Limit the size of the “<i>Central File</i>”; 2. Maximize workflow efficiency; and 3. Limit documentation access to only those responsible for any given scope of work. | |
| Geo-Referencing | <p>A. All BIM Models shall be geo-referenced to the Texas NAD-83 State Plane Zone appropriate to the individual project location.</p> | . |
| Existing Conditions Model(s) | <p>A. In cases of facility renovation projects, a copy of any existing BIM file(s) and associated Record Documentation will be made available to PSP.</p> <p>B. The model file(s) and documentation shall be utilized in the preparation of all related design and contract documents.</p> | |

[Return to Table of Contents](#)

* See next page for additional BIM File Types.

[Abbreviations](#)



| BIM STANDARDS – FILE TYPES | | (CONTINUED) |
|----------------------------|--|-------------|
| FILE TYPE | DEFINITION | LINKS |
| Templates | <p>A. The following standard files will be provided to PSP by TFC:</p> <ol style="list-style-type: none"> 1. Revit Model File with standardized information such as: <ol style="list-style-type: none"> a. Project Phasing (and associated graphic overrides); b. Graphic conventions; c. Wall (Partition) types; d. Door types; e. Door hardware functions; f. Room finish types. 2. Revit Annotation File with standardized information such as: <ol style="list-style-type: none"> a. Drawing sheet organization; b. Graphic conventions; c. Partition keys and details; d. Legends; e. Schedules. 3. Revit Titleblocks: 30x42 (Arch E1): <ol style="list-style-type: none"> a. Cover Sheet; b. Information Sheet; and c. All other sheets. <p>B. These template files are provided for the convenience of design professionals providing services to TFC for projects developed under TFC authority.</p> <p>C. The template files are intended to facilitate compliance with TFC design standards and must not replace the informed professional judgment of the PSP.</p> <p>D. It is solely the PSP’s responsibility to determine the proper application of the standardized information contained within these files.</p> | . |

[Return to Table of Contents](#)

* See next page for additional BIM File Types.

[Abbreviations](#)



| BIM STANDARDS – FILE TYPES (CONTINUED) | | |
|--|---|-------|
| FILE TYPE | DEFINITION | LINKS |
| Site Model | <p>A. Site Models are <i>Autodesk “Civil3D”</i> Project Drawings (or central data files).</p> <p>B. They contain all site related physical features of the project that are not integral with the building envelope:</p> <ol style="list-style-type: none"> 1. Utilities; 2. Topography; 3. Water Quality Ponds; 4. Stormwater Detention and Filtration Structures; 5. Planting Materials 6. Paving (Streets, parking, curb and gutter, driveways, walks, etc.); 7. Site stairs, ramps, and railings; 8. Retaining Walls; 9. Site furnishings. <p>C. Coordination with other disciplines:</p> <ol style="list-style-type: none"> 1. Periodically W-Block out information in “.dwg” format and make the file(s) available to the other project team members. | |

[Return to Table of Contents](#)

* See next page for additional BIM File Types.

[Abbreviations](#)



| BIM STANDARDS – FILE TYPES | | (CONTINUED) |
|----------------------------|---|--|
| FILE TYPE | DEFINITION | LINKS |
| Building Model | <p>A. TFC does not currently utilize Worksets.</p> <ol style="list-style-type: none"> 1. Before transmitting a “<i>Central Model File</i>” to TFC, “<i>Detach from Central</i>” and “<i>Detach and Discard Worksets</i>”. <p>B. Each Building Model File contains all physical features for a single building:</p> <ol style="list-style-type: none"> 1. Architectural; 2. Structural; 3. Mechanical; 4. Electrical; 5. Plumbing; and 6. Special Systems. <p>C. Shade Structures and pavilions are to be treated as independent buildings.</p> <p>D. Coordination with Civil3D:</p> <ol style="list-style-type: none"> 1. Periodically export to ADSK file format and make the file(s) available to the other project team members. | |
| Annotation | <p>A. Each design discipline will have a dedicated annotation file that references the appropriate Model File(s):</p> <ol style="list-style-type: none"> 1. Civil3D Files: 2. Revit Files: <ol style="list-style-type: none"> a. Insert the “<i>Central Model File</i>” as a link into the “<i>Central Annotation File</i>” using the following setting: <ol style="list-style-type: none"> i. Positioning: <i>Auto - Origin to Origin</i>. | <ul style="list-style-type: none"> • Drawing Sheet Organization |

[Return to Table of Contents](#)

[Abbreviations](#)



BIM STANDARDS – REVIT VIEW SETTINGS

| VIEW | SCALE | DETAIL LEVEL | MODEL GRAPHICS STYLE | SHADOWS | CROP REGION | PHASE | PHASE FILTER |
|------|-------|--------------|----------------------|---------|-------------|-------|--------------|
|------|-------|--------------|----------------------|---------|-------------|-------|--------------|

EXISTING

| | | | | | | | |
|---------------------|--------------|--------|-------------|-----|-----|----------|----------|
| Site Plans | 1" = 20'-0" | Coarse | Hidden Line | Off | Off | Existing | Show All |
| Floor Plans | 1/8" = 1'-0" | Medium | Hidden Line | Off | Off | Existing | Show All |
| Reflected Ceilings | 1/8" = 1'-0" | Medium | Hidden Line | Off | Off | Existing | Show All |
| Exterior Elevations | 1/8" = 1'-0" | Coarse | Hidden Line | Off | Off | Existing | Show All |
| Interior Elevations | 3/8" = 1'-0" | Medium | Hidden Line | Off | Off | Existing | Show All |
| Building Sections | 1/8" = 1'-0" | Medium | Hidden Line | Off | Off | Existing | Show All |
| Wall Sections | 3/4" = 1'-0" | Fine | Hidden Line | Off | Off | Existing | Show All |

DEMOLITION

| | | | | | | | |
|---------------------|--------------|--------|-------------|-----|-----|------------|----------------------|
| Site Plans | 1" = 20'-0" | Coarse | Hidden Line | Off | Off | Demolition | Show Previous + Demo |
| Floor Plans | 1/8" = 1'-0" | Medium | Hidden Line | Off | Off | Demolition | Show Previous + Demo |
| Reflected Ceilings | 1/8" = 1'-0" | Medium | Hidden Line | Off | Off | Demolition | Show Previous + Demo |
| Exterior Elevations | 1/8" = 1'-0" | Coarse | Hidden Line | Off | Off | Demolition | Show Previous + Demo |
| Interior Elevations | 3/8" = 1'-0" | Medium | Hidden Line | Off | Off | Demolition | Show Previous + Demo |
| Building Sections | 1/8" = 1'-0" | Medium | Hidden Line | Off | Off | Demolition | Show Previous + Demo |
| Wall Sections | 3/4" = 1'-0" | Fine | Hidden Line | Off | Off | Demolition | Show Previous + Demo |

[Return to Table of Contents](#)

* See next page for additional Revit Architecture View Settings Standards.

[Abbreviations](#)



| BIM STANDARDS – REVIT VIEW SETTINGS | | | | | | | (CONTINUED) |
|-------------------------------------|-------|--------------|----------------------|---------|-------------|-------|--------------|
| VIEW | SCALE | DETAIL LEVEL | MODEL GRAPHICS STYLE | SHADOWS | CROP REGION | PHASE | PHASE FILTER |

NEW CONSTRUCTION

| | | | | | | | |
|---------------------|--------------|--------|-------------|-----|-----|------------------|---------------------|
| Site Plans | 1" = 20'-0" | Coarse | Hidden Line | Off | Off | New Construction | Show Previous + New |
| Floor Plans | 1/8" = 1'-0" | Medium | Hidden Line | Off | Off | New Construction | Show Previous + New |
| Reflected Ceilings | 1/8" = 1'-0" | Medium | Hidden Line | Off | Off | New Construction | Show Previous + New |
| Exterior Elevations | 1/8" = 1'-0" | Coarse | Hidden Line | Off | Off | New Construction | Show Previous + New |
| Interior Elevations | 3/8" = 1'-0" | Medium | Hidden Line | Off | Off | New Construction | Show Previous + New |
| Building Sections | 1/8" = 1'-0" | Medium | Hidden Line | Off | Off | New Construction | Show Previous + New |
| Wall Sections | 3/4" = 1'-0" | Fine | Hidden Line | Off | Off | New Construction | Show Previous + New |

[Return to Table of Contents](#)

[Abbreviations](#)



| BIM STANDARDS – REVIT PARTITIONS | | |
|--|--|-------|
| ELEMENT | DEFINITION | LINKS |
| <p>Wall (Partition) Type Tags</p> | <p>A. When a “Wall Type” tag is placed, the correct partition type information is automatically populated.</p> <p>B. Partition Assembly Type Codes:</p> <ul style="list-style-type: none"> A = Metal stud framing with one layer of gypsum board on each side. B = Metal stud framing with two layers of gypsum board on each side. C = Metal stud furring partition with one layer of gypsum board on the finished side. D = Metal stud Shaftwall with one inch shaft-liner and varying layers of gypsum board on the finished face. E = Metal stud framing with resilient furring channels on one side and one layer of gypsum board on each finished face. F = Metal stud framing with resilient furring channels on one side and two layers of gypsum board on each finished face. G = Metal stud framed plumbing chase with 1 layer of gypsum board on each finished face. H = Partial height metal stud framing with one layer of gypsum board on each side. J = Fire rated metal stud partition with window(s) and deluge sprinklers. K = Concrete masonry units of varying widths. | |

[Return to Table of Contents](#)

* See next page for additional Revit Architecture Partition Standards.

[Abbreviations](#)



| BIM STANDARDS – REVIT PARTITIONS | | (CONTINUED) |
|---|---|-------------|
| ELEMENT | DEFINITION | LINKS |
| <p>Wall (Partition) Type Tags (Continued)</p> | <p>A. Core Width Codes: 1 = 1 5/8" Metal Studs 3 = 3 5/8" Metal Studs 4 = 4" Metal Studs – or - 4" Nominal Masonry 6 = 6" Metal Studs – or - 6" Nominal Masonry 7 = 7" Clear inside width at metal stud framed plumbing chase 8 = 8" Metal Studs – or - 8" Nominal Masonry 9 = 9" Clear inside width at metal stud framed plumbing chase 12 = 12" Nominal Masonry</p> <p>B. Partition Height Codes: A = Above Ceiling (to 6" above ceiling) (Set the "Top Offset" constraint of the "Wall" to six inches more than the height of the ceiling in question) C = Ceiling (to bottom of ceiling) (Attach the "Wall" to the "Ceiling") D = Deck High (to bottom of structural deck above) (Attach the "Wall" to the "Structural Floor or Roof" above) ## = Fixed Height (in inches to top of finish) (Set the "Unconnected Height" constraint of the "Wall" to the desired height of the partition at the top of the finished wall cap)</p> <p>C. Sound Rating Codes: S## (## = 2 digit STC rating number)</p> <p>D. Fire Rating Codes: F01 = 1 hour F02 = 2 hour F03 = 3 hour F04 = 4 hour F20 = 20 minutes F30 = 30 minutes F45 = 45 minutes F90 = 90 minutes</p> | |

[Return to Table of Contents](#)

* See next page for additional Revit Architecture Partition Standards.

[Abbreviations](#)



| BIM STANDARDS – REVIT PARTITIONS | | (CONTINUED) |
|--|--|-------------|
| ELEMENT | DEFINITION | LINKS |
| Wall (Partition) Type Tags (Continued) | A. When the “ <i>Wall Type</i> ” is changed, the tag automatically updates with the appropriate information for the new partition type. B. Custom “ <i>Wall Types</i> ” can be generated if necessary, but must include the following parametric “ <i>Identity Data</i> ” information: <ol style="list-style-type: none"> 1. <i>Assembly Code</i> - Edit Unifomat selection to match the wall construction ; 2. <i>Type Mark</i> – Assign a new partition type (use TFC naming conventions); 3. <i>Fire Rating</i> – Indicate if applicable. 4. <i>Fire Test #</i> - Provide UL assembly number if partition is fire rated; 5. <i>Sound Test #</i> - Provide STC rating if applicable; and 6. <i>UL URL</i> – Provide web address for specific UL assembly. | |
| Wall (Partition) Types | A. The Project Template file has a large library of TFC standard “ <i>Wall Types</i> ” (interior partitions) pre-loaded. B. All TFC standard “ <i>Wall Types</i> ” contain parameter text that matches the appropriate TFC standard partition type. C. “ <i>Wall Type</i> ” names are based on the Type Tag conventions above: <ol style="list-style-type: none"> 1. Example: “A3DS-51” <ol style="list-style-type: none"> a. Partition Type: A b. Core Width: 3 5/8” metal stud framing c. Partition Height: Deck high d. Sound Rating: STC 51 e. Fire Rating: None | |


[Return to Table of Contents](#)

[Abbreviations](#)



BIM STANDARDS – REVIT DOOR TYPES (KEY SCHEDULE)

The Project Template file has a library of TFC standard “Door Types” based on the function of the space the door is serving. Schedule information parameters are pre-defined as follows:



| | | | |
|--------------------------------------|--|---|--|
| <p>Hardware Abbreviations</p> | <p>CL – Closer EA – Electronic Access ED – Exit Device FBA – Flush Bolt (Automatic) PA – Power Assist KP – Kick Plate</p> | <p>LA – Latchset LO – Lockset (Office) LP – Lockset (Privacy) LS – Lockset (Storage) PP – Push Plate PU – Pull</p> | <p>RH – Robe Hook RM – Removable Mullion STW – Stop (Wall) SS – Smoke Seal TH – Threshold WS – Weatherstripping</p> |
|--------------------------------------|--|---|--|

[Return to Table of Contents](#)

* See next page for additional Revit Architecture Door Types.

[Abbreviations](#)



| BIM STANDARDS – REVIT DOOR TYPES (KEY SCHEDULE) | | | | | | | | | (CONTINUED) |
|---|----------------|-----------------|-----------|------------------|-------------|-----------------|----------------|--------------|-----------------------------|
| DOOR TYPE | WIDTH (inches) | HEIGHT (inches) | DOOR TYPE | DOOR MATERIAL | DOOR FINISH | FRAME TYPE | FRAME MATERIAL | FRAME FINISH | HARDWARE FUNCTIONS |
| Conference | 36 | 84 | GQ3 | Solid Core Wood | Transparent | Single | Aluminum | Anodized | LO, CL, STW |
| Conference (Enhanced) | 36 | 84 | GQ3 | Solid Core Wood | Transparent | Single Sidelite | Aluminum | Anodized | LO, CL, STW |
| Copy/Print | 36 | 84 | GQ5 | Solid Core Wood | Transparent | Single | Aluminum | Anodized | LA, STW |
| Corridor (Exit) | 36 | 84 | S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | LO, CL, STW |
| Restroom (Single) | 36 | 84 | S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | LP, CL, STW |
| Restroom (Common) | 36 | 84 | S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | PU, PP, KP, CL, STW |
| Server | 36 | 84 | S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | EA, LS, STW |
| Stair | 36 | 84 | S | Hollow Metal | Paint | Single | Hollow Metal | Paint | ED, CL, SS |
| Storage (Single) | 36 | 84 | S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | LS, STW |
| Storage (Double) | 72 | 84 | 2-S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | LS, RM |
| Entrance (Primary, Exterior) | 72 | 84 | 2GF | Aluminum / Glass | Anodized | Double | Aluminum | Anodized | EA, ED, FBA, CL, PA, TH, WS |
| Entrance (Secondary, Exterior) | 36 | 84 | S | Hollow Metal | Paint | Single | Hollow Metal | Paint | EA, ED, CL, PA, TH, WS |
| File | 36 | 84 | GQ5 | Solid Core Wood | Transparent | Single | Aluminum | Anodized | LS, CL, STW |
| Maintenance | 36 | 84 | S | Solid Core Wood | Transparent | Single | Hollow Metal | Paint | LS, CL, STW |
| MEP (Single) | 36 | 84 | S | Solid Core Wood | Transparent | Single | Hollow Metal | Paint | LS, CL, STW |
| MEP (Double) | 72 | 84 | 2-S | Solid Core Wood | Transparent | Single | Hollow Metal | Paint | LS, CL |

[Return to Table of Contents](#)

* See next page for additional Revit Architecture Door Types.

[Abbreviations](#)



| BIM STANDARDS – REVIT DOOR TYPES (KEY SCHEDULE) | | | | | | | | | (CONTINUED) |
|---|----------------|-----------------|-----------|-----------------|-------------|-----------------|----------------|--------------|---------------------|
| DOOR TYPE | WIDTH (inches) | HEIGHT (inches) | DOOR TYPE | DOOR MATERIAL | DOOR FINISH | FRAME TYPE | FRAME MATERIAL | FRAME FINISH | HARDWARE FUNCTIONS |
| Office | 36 | 84 | S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | LO, RH, STW |
| Office Suite | 36 | 84 | S | Solid Core Wood | Transparent | Single Sidelite | Aluminum | Anodized | LO, STW |
| Restroom (Single) | 36 | 84 | S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | LP, CL, STW |
| Restroom (Common) | 36 | 84 | S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | PP, PU, KP, CL, STW |
| Server | 36 | 84 | S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | EA, LS, STW |
| Stair | 36 | 84 | S | Hollow Metal | Paint | Single | Hollow Metal | Paint | ED, CL, SS |
| Storage (Single) | 36 | 84 | S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | LS, STW |
| Storage (Double) | 72 | 84 | 2-S | Solid Core Wood | Transparent | Single | Aluminum | Anodized | LS, RM |

[Return to Table of Contents](#)

[Abbreviations](#)



| BIM STANDARDS – REVIT ROOM STYLES (KEY SCHEDULE) | | | |
|--|-------------------------|----------------|---|
| The Project Template file has a library of TFC standard “Room Styles” with Finish Schedule information parameters pre-defined. | | | |
| ROOM TYPE | FLOOR | BASE | CEILING |
| Break | VCT | 4” Rubber Cove | 2’x2’ ACT |
| Conference | Carpet Tile | 4” Rubber Cove | 2’x2’ ACT |
| Conference (Enhanced) | Carpet Tile | Wood (Stained) | 2’x2’ ACT, Painted Gypsum Board |
| Copy / Print | VCT | 4” Rubber Cove | 2’x2’ ACT |
| Corridor | Carpet Tile | 4” Rubber Cove | 2’x2’ ACT |
| File | Carpet Tile | 4” Rubber Cove | 2’x2’ ACT |
| Maintenance | Sealed Concrete | 4” Rubber Cove | 2’x2’ ACT |
| MEP | Sealed Concrete | None | 2’x2’ ACT |
| Office | Carpet Tile | 4” Rubber Cove | 2’x2’ ACT |
| Restroom | Tile | Tile | Painted Gypsum Board |
| Server | Static Dissipative Tile | 4” Rubber Cove | 2’x2’ ACT |
| Shower | Tile | Tile | Water Resistant Gypsum Board (Epoxy Paint) |
| Stair | Sealed Concrete | None | 2’x2’ ACT, Painted Structure |
| Storage (General) | Sealed Concrete | None | Painted Structure |
| Storage (Office) | Carpet Tile | 4” Rubber Cove | 2’x2’ ACT |

[Return to Table of Contents](#)

[Abbreviations](#)



| BIM STANDARDS – REVIT MATERIALS | | |
|--|-----------------------------|------------------------------|
| The Project Template file has a library of TFC standard “ <i>Materials</i> ” with Design Selections Schedule information parameters pre-defined. | | |
| MARK | MATERIAL CLASS | DESCRIPTION |
| AT-AC01 | Acoustical Treatment (AT) | Acoustical Coating (AC) |
| AT-SAP01 | Acoustical Treatment (AT) | Sound Absorptive Panel (SAP) |
| AT-SRP01 | Acoustical Treatment (AT) | Sound Reflective Panel (SRP) |
| AW-WD01 | Architectural Woodwork (AW) | Wood Trim (WD) |
| AW-WP01 | Architectural Woodwork (AW) | Wood Panel (WP) |
| AW-WV01 | Architectural Woodwork (AW) | Wood Veneer (WV) |
| CF-BR01 | Concrete Finish (CF) | Broom Finished Concrete (BR) |
| CF-CS01 | Concrete Finish (CF) | Clear Sealer (CS) |
| CF-EA01 | Concrete Finish (CF) | Exposed Aggregate (EA) |
| CF-IC01 | Concrete Finish (CF) | Integral Color (IC) |
| CF-POL01 | Concrete Finish (CF) | Polished (POL) |
| CF-RF01 | Concrete Finish (CF) | Rough Formwork (RF) |
| CF-SB01 | Concrete Finish (CF) | Sandblasted (SB) |
| CF-ST01 | Concrete Finish (CF) | Stained (ST) |
| CF-TRW01 | Concrete Finish (CF) | Trowel Finished (TR) |

[Return to Table of Contents](#)

* See next page for additional Revit Materials.

[Abbreviations](#)



| BIM STANDARDS – REVIT MATERIALS | | | (CONTINUED) |
|--|------------------------------|--|-------------|
| MARK | MATERIAL CLASS | DESCRIPTION | |
| CL-AT01 | Ceilings (CL) | Acoustical Ceiling Tile (AT) | |
| CL-GD01 | Ceilings (CL) | Acoustical Ceiling Grid (GD) | |
| CL-LS01 | Ceilings (CL) | Linear Ceiling System (LS) - Wood or Metal | |
| CW-HG01 | Casework (CW) | Hardware Grommet (HG) | |
| CW-HP01 | Casework (CW) | Hardware Pull (HP) | |
| DS-CB01 | Visual Display Surfaces (DS) | Chalk Board (CB) | |
| DS-MB01 | Visual Display Surfaces (DS) | Marker Board (MB) | |
| DS-TB01 | Visual Display Surfaces (DS) | Tack Board (TB) | |
| FL-AF01 | Flooring (FL) | Access Flooring (AF) | |
| FL-CK01 | Flooring (FL) | Cork (CK) | |
| FL-CP01 | Flooring (FL) | Carpet (CP) - Broadloom or Tile | |
| FL-FA01 | Flooring (FL) | Fluid Applied (FA) | |
| FL-LS01 | Flooring (FL) | Linoleum Sheet (LS) | |
| FL-LT01 | Flooring (FL) | Linoleum Tile (LT) | |
| FL-SDT01 | Flooring (FL) | Static Dissipative Tile (SDT) | |
| FL-TZ01 | Flooring (FL) | Terrazzo (TZ) | |
| FL-VS01 | Flooring (FL) | Vinyl Sheet (VS) | |

[Return to Table of Contents](#)

* See next page for additional Revit Materials.

[Abbreviations](#)



| BIM STANDARDS – REVIT MATERIALS | | | (CONTINUED) |
|--|-----------------------|---|--------------------|
| MARK | MATERIAL CLASS | DESCRIPTION | |
| FL-VT01 | Flooring (FL) | Vinyl Tile (VT) - VCT, Solid Vinyl.. | |
| FL-WD01 | Flooring (FL) | Wood (WD) | |
| GF-CK01 | General Finishes (GF) | Cork (CK) | |
| GF-CT01 | General Finishes (GF) | Ceramic Tile (CT) | |
| GF-CTG01 | General Finishes (GF) | Ceramic Tile Grout (CTG) | |
| GF-FB01 | General Finishes (GF) | Fabric (FB) | |
| GF-M01 | General Finishes (GF) | Metal (M) | |
| GF-PL01 | General Finishes (GF) | Plastic Laminate (PL) | |
| GF-QS01 | General Finishes (GF) | Quartz Surface (QS) | |
| GF-SS01 | General Finishes (GF) | Solid Surface (SS) | |
| GF-ST01 | General Finishes (GF) | Stone Tile (ST) | |
| GL-G01 | Glazing (GL) | Glass (G) - Tempered, Decorative, Mirrored, LCD.. | |
| GL-PG01 | Glazing (GL) | Plastic Glazing (PG) | |
| GL-SF01 | Glazing (GL) | Surface Applied Film (SF) | |

[Return to Table of Contents](#)

* See next page for additional Revit Materials.

[Abbreviations](#)



| BIM STANDARDS – REVIT MATERIALS | | | (CONTINUED) |
|--|-----------------------------|---|-------------|
| MARK | MATERIAL CLASS | DESCRIPTION | |
| PC-CS01 | Paints and Coatings (PC) | Clear Sealer (CS) | |
| PC-HP01 | Paints and Coatings (PC) | High Performance / Special Coatings (HP) - Fire Resistive, Galvanizing... | |
| PC-IP01 | Paints and Coatings (PC) | Interior Paint (IP) | |
| PC-IS01 | Paints and Coatings (PC) | Interior Stain (IS) | |
| PC-IT01 | Paints and Coatings (PC) | Interior Textured Coating (IT) | |
| PC-WR01 | Paints and Coatings (PC) | Water Repellant Coating (WR) | |
| PC-XP01 | Paints and Coatings (PC) | Exterior Paint (XP) | |
| PC-XS01 | Paints and Coatings (PC) | Exterior Stain (XS) | |
| PC-XT01 | Paints and Coatings (PC) | Exterior Textured Coating (XT) | |
| WB-R401 | Wall Base (WB) | Rubber 4" (R4) | |
| WB-R601 | Wall Base (WB) | Rubber 6" (R6) | |
| WB-V401 | Wall Base (WB) | Vinyl 4" (V4) | |
| WB-V601 | Wall Base (WB) | Vinyl 6" (V6) | |
| WB-WD401 | Wall Base (WB) | Wood 4" (WD4) | |
| WB-WD601 | Wall Base (WB) | Wood 6" (WD6) | |
| WF-FP01 | Interior Wall Finishes (WF) | Fabric Panel (FP) | |
| WF-WC01 | Interior Wall Finishes (WF) | Wall Covering (WC) – Fabric, Vinyl... | |

[Return to Table of Contents](#)

* See next page for additional Revit Materials.

[Abbreviations](#)



| BIM STANDARDS – REVIT MATERIALS | | |
|--|------------------------|---|
| | | (CONTINUED) |
| MARK | MATERIAL CLASS | DESCRIPTION |
| WP-CG01 | Wall Protection (WP) | Corner Guard (CG) |
| WP-WG01 | Wall Protection (WP) | Wall Guard (WG) |
| WT-BL01 | Window Treatments (WT) | Blinds (BL) |
| WT-DR01 | Window Treatments (WT) | Drapery / Curtain (DR) |
| WT-SH01 | Window Treatments (WT) | Window Shades (SH) |
| XF-BK01 | Exterior Finishes (XF) | Brick (BK) |
| XF-CFS01 | Exterior Finishes (XF) | Cement Fiberboard Siding (CFS) |
| XF-CM01 | Exterior Finishes (XF) | Concrete Masonry Unit (CM) |
| XF-CP01 | Exterior Finishes (XF) | Cement Plaster (CP) |
| XF-GU01 | Exterior Finishes (XF) | Glass Unit Masonry (GU) |
| XF-LS01 | Exterior Finishes (XF) | Linear Soffit System (LS) - Wood or Metal |
| XF-MP01 | Exterior Finishes (XF) | Metal Panel (MP) |
| XF-PC01 | Exterior Finishes (XF) | Precast Concrete (PC) |
| XF-SP01 | Exterior Finishes (XF) | Simulated Plaster (SP) – EIFS... |
| XF-SS01 | Exterior Finishes (XF) | Simulated Stone (SS) |
| XF-ST01 | Exterior Finishes (XF) | Stone (ST) |
| XF-WS01 | Exterior Finishes (XF) | Wood Siding (WS) |

[Return to Table of Contents](#)

[Abbreviations](#)



| BIM STANDARDS –RECOMMENDED PRACTICES | | |
|--|--|--|
| TOPIC | RECOMMENDATION | LINKS |
| Model Planning & Coordination | A. Utilize a BIM Planning and Coordination Document such as in Appendix M (or a similar document) to identify authorship responsibility for each portion of the Building Model Central File. B. Do not modify or manipulate elements that other PSPs are responsible for. | <ul style="list-style-type: none"> · Appendix M - BIM Planning Document |
| Revit File Maintenance | A. Audit the Central Files periodically to identify and correct file irregularities. B. Compact the Central files at the end of each work day to reduce file size. | |
| Digital Data Agreement | A. It is TFC’s intent to share the Project BIM Model with the Contractor for their use in project scheduling and coordination. B. TFC recommends that the PSP include a Division 1 Specification requirement for the Contractor, Subcontractors, and Suppliers to enter into a Digital Data Licensing Agreement such as AIA Document C106-2007. | <ul style="list-style-type: none"> · AIA Documents |
| Digital Coordination & Review | A. TFC utilizes Autodesk’s free “Design Review” software to review all documentation submitted by PSPs. We encourage all PSPs to coordinate with each other using the same process. | <ul style="list-style-type: none"> · Autodesk Design Review Software |
| Revit Productivity | A. Download and utilize software extensions and bonus tools available from the Autodesk Subscription Center | |

[Return to Table of Contents](#)

* See next page for additional Recommended Practices.

[Abbreviations](#)



| APPENDICES | | |
|------------|--|---|
| NUMBER | TITLE | DESCRIPTION |
| A | Reserved for Future Use | A. (Previously "Standard Procedure for Measurement") |
| B | Reserved for Future Use | A. (Previously "Sustainable Building Practices") |
| C | Indoor Air Quality Guidelines | A. Design and construction requirements for meeting indoor air quality criteria. |
| D | Reserved for Future Use | A. (Previously "Energy Simulation Software"). |
| E | Reserved for Future Use | A. (Previously "Resources") |
| F | Landscaping Design Standards | A. Standards for the selection and specification of water conserving landscape materials. |
| G | Facilities Programming Guidelines | A. Recommended practices for the programming of facilities to be developed under the authority of TFC. |
| H | DPS Standards (08/08/2006) | A. Design standards for DPS projects. |
| I | Reserved for Future Use | A. (Previously "Common TAS Errors") |
| J | DPS Design Issues | A. A sampling of common design issues and preferred solutions on DPS projects. |
| K | Project Manual and Specification Section Formats | A. Standard formatting for: 1. Project Manual Cover and signature pages ; and 2. Specification sections . B. Standards for the content of select specification sections. |
| L | Space Allocation Program | A. Standard spreadsheet for recording square footages for proposed buildings, departments, and individual spaces. |
| M | BIM Planning and Coordination Document | A. Matrix for assigning BIM scopes of work by discipline. |

[Return to Table of Contents](#)

[Abbreviations](#)



WEB LINKS INCLUDED IN THIS DOCUMENT

STATE OF TEXAS

| | | |
|-------------|---|---|
| DIR | Department of Information Resources | http://www.dir.state.tx.us/ |
| DPS | Department of Public Safety | http://www.txdps.state.tx.us/index.htm |
| HSC | Health & Safety Code (Texas) | http://www.statutes.legis.state.tx.us/?link=GV |
| SECO | State Energy Conservation Office | http://www.seco.cpa.state.tx.us/index.php |
| | Texas Design Standard Compliance Forms | http://www.seco.cpa.state.tx.us/sa_codes.html#anchor01 |
| | AHRAE 90.1 and RETScreen Software Adoption | http://www.seco.cpa.state.tx.us/sa_codes.html#sb982 |
| | SECO Suggested Water Efficiency Standards | http://www.seco.cpa.state.tx.us/tbec/waterconservation.php |
| | SECO Approved Methodologies | http://www.seco.cpa.state.tx.us/sa_codes.html |
| SFMO | State Fire Marshal's Office | http://www.tdi.state.tx.us/fire/index.html |
| TCEQ | Texas Commission on Environmental Quality | http://www.tceq.state.tx.us/ |
| | TCEQ Construction Activities Regulations | http://www.tceq.state.tx.us/permitting/water_quality/stormwater/TXR15_AIR.html |
| TDI | Texas Department of Insurance | http://www.tdi.state.tx.us/ |
| TDLR | Texas Department of Licensing and Regulation – Home Page | http://www.license.state.tx.us/index.htm |
| | Document Submission Requirements | http://www.license.state.tx.us/ab/abrules.htm#6850 |
| | EAB (Elimination of Architectural Barriers) | http://www.license.state.tx.us/ab/ab.htm |
| | Fee Schedule | http://www.license.state.tx.us/ab/abfees.htm |
| | Online Registration | https://www.license.state.tx.us/ABProjectRegistrationOnline/ |
| | TAS (Texas Accessibility Standards) | http://www.license.state.tx.us/ab/abtas.htm#toc |
| | Architectural Barriers Technical Memoranda | http://www.license.state.tx.us/ab/techmemos.htm |
| TAC | Texas Administrative Code | http://info.sos.state.tx.us/pls/pub/tacctx\$.startup |

[Return to Table of Contents](#)

* See next page for additional Web Links.

[Abbreviations](#)



| WEB LINKS INCLUDED IN THIS DOCUMENT | | (CONTINUED) |
|---|---|---|
| TFC | Texas Facilities Commission – Home Page | http://www.tfc.state.tx.us/ |
| | FDC (Facilities Design and Construction) | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/ |
| | EM (Energy Management) | http://www.tfc.state.tx.us/divisions/facilities/prog/division-of-energy-management-and-plant-operations/office-of-energy-management/ |
| | Guidelines / Standards | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex |
| | Electronic Project Management Control System | http://www.3di.com/impact/tfc/ |
| | OM (Operations and Maintenance) | http://www.tfc.state.tx.us/divisions/facilities/prog/division-of-energy-management-and-plant-operations/plant-operations/ |
| | HUB (Historically Underutilized Business Program) | |
| | IPD (Internal Procurement Division) | http://www.tfc.state.tx.us/divisions/commissionadmin/prog/HUB/ |
| | PAM (Planning and Asset Management) | http://www.tfc.state.tx.us/divisions/facilities/prog/planning |
| | UGC / SGC (Uniform and Supplementary General Conditions) | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex |
| | 2012 A-E Guidelines | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex/01 - 2012 A-E GUIDELINES.pdf |
| | 2012 A-E Guidelines Appendix C (Indoor Air Quality Guidelines) | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex/02 2012 A-E Guidelines Appendix C indoor air.pdf |
| | 2012 A-E Guidelines Appendix F (Landscaping Design Standards) | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex/03 - 2012 A-E Guidelines Appendix F landscp.pdf |
| | 2012 A-E Guidelines Appendix G (Facilities Programming Guidelines) | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex/04 - 2012 A-E Guidelines Appendix G fac prog guide.pdf |
| | 2012 A-E Guidelines Appendix H (DPS Standards (08/08/2006)) | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex/05 - 2012 A-E Guidelines Appendix H -dps stds 8.8.06.pdf |
| | 2012 A-E Guidelines Appendix J (DPS Design Issues) | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex/06 - 2012 A-E Guidelines Appendix J DPS Design Issues.pdf |
| | 2012 A-E Guidelines Appendix K (Project Manual Cover and Signature Pages) | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex/07 - 2012 A-E Guidelines (Appendix K) Proj Manual Cvr.doc |
| | 2012 A-E Guidelines Appendix K (Specification Sections Format) | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex/08 - 2012 A-E Guidelines (Appendix K) Spec Format.doc |
| 2012 A-E Guidelines Appendix L (Space Allocation Program) | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex/09 - 2012 A-E Guidelines (Appendix L) Space Alloc Program.xls | |
| 2012 A-E Guidelines Appendix M (BIM Planning and Coordination Document) | http://www.tfc.state.tx.us/divisions/facilities/prog/construct/formsindex/10 - 2012 A-E Guidelines (Appendix M) BIM Planning Doc.xls | |

[Return to Table of Contents](#)

* See next page for additional Web Links.

[Abbreviations](#)



WEB LINKS INCLUDED IN THIS DOCUMENT (CONTINUED)

| | | |
|------------|---|---|
| TGC | Texas Statutes - Government Code | http://www.statutes.legis.state.tx.us/?link=GV |
| THC | Texas Historical Commission | http://www.thc.state.tx.us/index.shtml |

FEDERAL and LOCAL

| | | |
|-------------|---------------------------------|---|
| ADA | Americans With Disabilities Act | http://www.ada.gov/ |
| ADAS | ADA Standards | http://www.ada.gov/stdspdf.htm |
| COA | City of Austin | http://www.austintexas.gov/ |

CAPITOL VIEW CORRIDOR

| | | |
|-----------------|--|---|
| TGC 3151 | Preservation of View of State Capitol | http://www.statutes.legis.state.tx.us/?link=GV |
| LDC | Land Development Code (City of Austin) | http://www.amlegal.com/nxt/gateway.dll/Texas/austin/title25landdevelopment?f=templates\$fn=default.htm\$3.0\$vid=amlegal:austin_tx |

CODES AND REFERENCE STANDARDS

| | | |
|-------------------------|---|---|
| AIA D101-1995 | Methods of Calculating the Area and Volume of Buildings; | https://www.aiabookstore.com/aia-documents/aia-documents-d-series.html |
| ANSI | American National Standards Institute | http://www.ansi.org/ |
| ASHRAE | The American Society of Heating, Refrigerating and Air-Conditioning Engineers | http://www.ashrae.org/ |
| ASHRAE 90.1 | Energy Conservation Design Standard for State-Funded Buildings | http://www.techstreet.com/lists/ashrae_standards.tpl |
| Comcheck | Energy Code Compliance Checking Software | http://energycode.pnl.gov/COMcheckWeb/ |
| CSI MasterFormat | 2004/2011 Edition Numbers and Titles | http://www.csinet.org/Main-Menu-Category/CSI-Store/6 |
| ICC | <u>International Code Council ICC Store</u> | http://www.iccsafe.org/Store/Pages/default.aspx |
| | Free E-Codes (2009) | http://publicecodes.citation.com/icod/IC-P-2009-000019.htm |
| | Free E-Codes (2012) | http://publicecodes.citation.com/icod/IC-P-2012-000019.htm |
| NFPA | National Fire Protection Association – Home Page | http://www.nfpa.org/ |
| | NFPA 101 - Life Safety Code | http://www.nfpa.org/aboutthecodes/AboutTheCodes.asp?DocNum=101 |
| | NFPA 70 - National Electrical Code | http://www.nfpa.org/aboutthecodes/AboutTheCodes.asp?DocNum=70 |
| | NFPA 70E - Standard for Electrical Safety in the Workplace | http://www.nfpa.org/aboutthecodes/AboutTheCodes.asp?DocNum=70E |

[Return to Table of Contents](#)

* See next page for additional Web Links.

[Abbreviations](#)



WEB LINKS INCLUDED IN THIS DOCUMENT

(CONTINUED)

SOFTWARE

| | |
|-------------------------------|---|
| Autodesk "Autocad" | http://usa.autodesk.com/adsk/servlet/pc/index?id=13779270&siteID=123112 |
| Autodesk "Autocad Civil 3D" | http://usa.autodesk.com/civil-3d/ |
| Autodesk "DWF Writer" | Autodesk - Autodesk DWF Writer |
| Autodesk "Navisworks" | http://usa.autodesk.com/adsk/servlet/index?id=10571060&siteID=123112 |
| Autodesk "Revit Architecture" | http://usa.autodesk.com/revit/ |
| Autodesk "Revit MEP" | http://usa.autodesk.com/revit/ |
| Autodesk "Revit Structure" | http://usa.autodesk.com/revit/ |
| | |

[Return to Table of Contents](#)

[Abbreviations](#)



INDEX

| | | | |
|---|-------------------------------|---|------------------------------------|
| Abbreviations | 3, 4 | CADD Standards (Area Calculations) | 52 |
| Accessibility (Registration and Review) | 43 | CADD Standards (Blocks)..... | 50 |
| Accessibility (Review and Inspection)..... | 15 | CADD Standards (Colors)..... | 50 |
| ADA Standards | 11 | CADD Standards (Dimensions) | 51 |
| Adjacency and Stacking Diagrams | 22 | CADD Standards (Drawing Origin) | 51 |
| Alternative Energy Evaluations (TFC Responsibility) | 9 | CADD Standards (Existing Conditions Files)..... | 49 |
| Appendices | 72 | CADD Standards (Hatching) | 51 |
| ASHRAE 90.1 | 8, 11, 28, 29, 30, 36, 37, 41 | CADD Standards (Layers) | 51 |
| ASHRAE 90.1 (SECO Adoption) | 11 | CADD Standards (Limitations of Use)..... | 5, 48 |
| Bid Documents..... | 42 | CADD Standards (Linetypes)..... | 50 |
| BIM Model (Submission Procedures) | 13 | CADD Standards (Purge/Audit) | 52 |
| BIM Model Planning and Coordination (Recommended Practices). 71 | | CADD Standards (Purpose)..... | 49 |
| BIM Models (Content) | 25, 31, 38, 42, 44 | CADD Standards (Quality Check)..... | 52 |
| BIM Models (Record Documents)..... | 45 | CADD Standards (Reference Files) | 50 |
| BIM Standards (Annotation Files) | 56 | CADD Standards (Scale) | 50 |
| BIM Standards (Building Model Files)..... | 56 | CADD Standards (Template File) | 49 |
| BIM Standards (Deviation From) | 48 | CADD Standards (Text and Fonts) | 51 |
| BIM Standards (Existing Conditions Models)..... | 53 | CADD Standards (Units) | 50 |
| BIM Standards (File Types) | 53, 54, 55, 56 | Capitol Views..... | 8 |
| BIM Standards (Geo-Referencing) | 53 | Change Documentation | 44 |
| BIM Standards (Purpose)..... | 48 | Change Orders..... | 7 |
| BIM Standards (Recommended Practices)..... | 71 | City of Austin Land Development Code | 8 |
| BIM Standards (Revit Door Types) | 62, 63, 64 | Civil 3D Files (Submission Procedures)..... | 13 |
| | 66, 67, 68, 69, 70 | Clash Detection | 31 |
| BIM Standards (Revit Partitions)..... | 59, 60, 61 | Codes and Standards | 11 |
| BIM Standards (Revit Room Styles) | 65 | Contract Documents (Consolidated Set) | 44 |
| BIM Standards (Revit View Settings)..... | 57, 58 | CSI MasterFormat (2004 Edition) | 40 |
| BIM Standards (Revit Wall Type Tags)..... | 59, 60, 61 | Data / Calculations | 37, 41, 43 |
| BIM Standards (Revit Wall Types Library)..... | 61 | Digital Coordination & Review (Recommended Practices)..... | 71 |
| BIM Standards (Site Mode Files) | 55 | Digital Data Agreement (Recommended Practices) | 71 |
| BIM Standards (Software Requirements) | 48 | Document Review (TFC Responsibility) | 7 |
| BIM Standards (Template Files) | 54 | Document Submission Procedures..... | 13, 14, 15 |
| BIM Standards (TFC Adoption)..... | 5, 48 | Drawing Standards (Document Organization) | 46, 47 |
| Building Area (Calculation Method) | 25 | Drawing Standards (Drawing Numbering) | 46 |
| Building Area (Reporting Requirements) | 23 | Drawings (Content) | 26, 28, 32, 33, 34, 35, 36, 39, 40 |
| CADD / BIM Standards | 48 | <i>Drawings (Electronic Document Submission Procedures)</i> | 13 |
| CADD Standards..... | 49, 50, 51, 52 | Electronic Documents (Submission Procedures)..... | 13, 14 |
| CADD Standards (Accuracy) | 49 | | |



| | |
|--|--|
| Electronic File Submission Format . 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45 | Round Trip Review Process..... 13 |
| Elimination of Architectural Barriers (Technical Memoranda)..... 11 | Round Trip Review Process (Diagram)..... 16 |
| Energy / Water Conservation (TFC Responsibility) 8 | Schedule for Delivery of Services 19, 25, 31, 38, 42, 44 |
| Energy Efficient Architectural & Engineering Design Alternatives ... 28 | SECO (Compliance Forms) 15 |
| Estimate of Probable Project Construction Cost..... 20, 25, 31, 38 | SECO (State Energy Conservation Office) 8 |
| Executive Summary Report 19, 25, 31, 38, 42 | SECO (Texas Design Standard Compliance Forms)..... 15, 43 |
| Existing Conditions Analysis 21 | SECO (Water Conservation Standard) 29 |
| FDC Forms Index 5 | SECO Documentation 43 |
| Guidelines/Standards (Applicability) 5 | SECO Suggested Water Efficiency Standards 8 |
| Guidelines/Standards (Intent) 5 | Site Inspections 12 |
| Guidelines/Standards (Periodic Revisions)..... 5 | Software Requirements..... 5 |
| Hazardous Materials 12 | Space Allocation Program..... 23, 25, 31, 38, 42 |
| Hazardous Materials (Certification letter)..... 43 | Specifications (Content) 28, 37, 40 |
| Historical Status (Determination and Compliance) 15 | State Agencies 6 |
| HSC 425 (Regulation of Certain Outdoor Lighting) 11 | State Agencies (Other Key Agencies) 6 |
| International Code Council..... 11 | State Agencies (TFC)..... 6 |
| Layout Diagrams 22 | State Agencies (Using Agency) 6 |
| Lighting Pollution (Exterior)..... 11 | Statutory Charge (of TFC)..... 5 |
| Narratives / Analyses (Content) 29 | Statutory Requirements 7, 8, 9, 10, 11, 12 |
| Narratives / Analyses / Evaluations 24, 37, 41, 42 | Submission Content (Construction) 44 |
| NFPA 101 11 | Submission Content (Contract Bidding and Award)..... 42, 43 |
| NFPA 101 (SFMO Adoption)..... 11 | Submission Content (Contract Documents)..... 38, 39, 40, 41 |
| NFPA 70 (NEC)..... 11 | Submission Content (Design Development) 31, 32, 33, 34, 35, 36, 37 |
| NFPA 70E 11 | Submission Content (Mobilization / Pre-Design) 18, 19, 20, 21, 22, 23, 24 |
| Partition Types (Assembly Type Codes)..... 59 | Submission Content (Schematic Design) 25, 26, 27, 28, 29, 30 |
| Partition Types (Core Width Codes) 60 | Submission Content (Warranty) 45 |
| Partition Types (Custom) 61 | Submission Format Requirements..... 17 |
| Partition Types (Fire Rating Codes)..... 60 | Submission Milestones 17 |
| Partition Types (Height Codes)..... 60 | Submission Milestones (Construction)..... 18 |
| Partition Types (Sound Rating Codes) 60 | Submission Milestones (Contract Bidding and Award) 18 |
| Printed Documents (Submission Procedures) 14 | Submission Milestones (Contract Documents) 18 |
| Project Funding 7 | Submission Milestones (Design Development) 17 |
| Project Implementation Plan 19 | Submission Milestones (Mobilization / Pre-design) 17 |
| Project Objective Statement..... 19 | Submission Milestones (Schematic Design) 17 |
| Record Documents 45 | Submission Milestones (Warranty) 18 |
| Response to Owner Comments (Submission Procedures) 14 | Submission Procedures 13, 14, 15 |
| Revit File Maintenance (Recommended Practices)..... 71 | Supplemental General Conditions 12 |
| Revit Files (Submission Procedures)..... 13 | SWPPP (Storm Water Polution Prevention Plan) 8 |
| Room Data Sheets 21 | Table of Contents 2 |



| | | | |
|---|----|---|-----------------|
| TAC (Texas Administrative Code) | 8 | Purchase of Automated Information Systems)..... | 7 |
| TAC, 25,1, 295, C, 295.34 | 12 | TGC 2158 (Purchasing Miscellaneous Provisions for Purchase of | |
| TAS Standards..... | 11 | Certain Goods and Services) | 7 |
| TCEQ (Texas Commission for Environmental Quality) | 15 | TGC 2161 (Historically Underutilized Businesses) | 7 |
| TCEQ Construction Activities Legislation | 8 | TGC 2162 State Council on Competitive Government)..... | 7 |
| TDLR (Document Submission Requirements)..... | 15 | TGC 2163 (Commercially Available Activities) | 7 |
| TDLR (Fee Schedule) | 15 | TGC 2165..... | 5 |
| TDLR (Online Registration)..... | 15 | TGC 2165 (State Buildings, Grounds, and Property)..... | 7 |
| Technical Requirements | 20 | TGC 2166 (Building Construction and Acquisition)..... | 7, 8, 9, 12, 28 |
| TFC (Enabling Statute) | 7 | TGC 2167 (Lease of Space for State Agencies)..... | 7 |
| TFC (FDC Activities and Limits)..... | 7 | TGC 3151 (Preservation of View of State Capitol) | 8 |
| TGC 2151 (State Purchasing and General Services Act)..... | 7 | TGC 417 (State Fire Marshal)..... | 11 |
| TGC 2152 (Texas Facilities Commission) | 7 | TGC 469 (Elimination of Architectural Barriers)..... | 11 |
| TGC 2155 (Purchasing | | THC (Texas Historical Commission)..... | 15 |
| General Rules and Procedures)..... | 7 | Uniform and Supplemental General Conditions..... | 12 |
| TGC 2156 (Purchasing Methods) | 7 | Uniform General Conditions..... | 12 |
| TGC 2157 (Purchasing | | Web Links..... | 73, 74, 75 |
| Return to Table of Contents | | | |